

Max. Lifting Capacity: 250 t x 4.6 m Max. Crane Boom Length: 76.2 m Max. Long Boom Length: 91.4 m


Max. Fixed Jib Combination: 76.2 + 30.5m Max. Tower Jib Combination: 64.1 + 51.8 m



# CONFIGURATION









# **SPECIFICATIONS**



# **Power Plant**

Model: Hino diesel engine P11C-UN

**Type:**Water-cooled, direct fuel injection, with turbocharger Compiles with NRMM (Europe) Stage IIIA and US EPA Tier III.

Displacement: 10.520 liters

Rated Power:247 kW at 2,000 min<sup>-1</sup> {rpm} (ISO)

Max. torque: 1,300 N·m/1,500 min-1

Cooling system: Liquid, recirculating bypass

Starter: 24 V/6.0 kW

Radiator: Corrugated type core, thermostatically controlled Air cleaner: Dry type with replaceable paper element Throttle: Electric throttle control, twist grip type

Fuel filter: Replaceable paper element

Batteries: Two 12V, 136Ah/5HR capacity batteries, series con-

nected.

Fuel tank capacity: 400 liters



# **Hydraulic System**

Four variable displacement piston pumps are driven by heavyduty pump drive. Two of variable displacement pumps are used in the main hook hoist circuit, auxiliary hook hoist circuit, and each propel circuit. One of the other two pumps is used in the boom hoist circuit and third hoist circuit. The other is used in the swing circuit.

**Control:** Full-flow hydraulic control system for infinitely variable pressure to front and rear drums, boom hoist brakes and clutches. Controls respond instantly to the touch, delivering smooth function operation.

Cooling: Oil-to-air heat exchanger (plate-fin type)

**Filtration:** Full-flow and bypass type with replaceable element **Electrical system:** All wiring corded for easy servicing, individual fused branch circuits.

# Max. relief valve pressure:

Load hoist, boom hoist and propel system:

31.9 MPa {325 kgf/cm²}

Swing system: 27.5 MPa {280 kgf/cm²} Control system: 5.4 MPa {55 kgf/cm²}

Reservoir capacity: 600 liters



# **Boom Hoisting System**

Powered by a hydraulic motor through a planetary reducer. **Brake:** A spring-set, hydraulically released multiple-disc brake is mounted on the boom hoist motor and operated through a counter-balance valve.

Drum lock: External ratchet for locking drum.

**Drum:** Double drum, grooved for 22 mm dia. wire rope.

**Line speed:** Double line on first drum layer **Hoisting/Lowering:** 27 to 2 m/min x 2

Diameter of wire ropes

Boom auv line: 38 mm

Boom hoist reeving: 16 parts of 22 mm dia.high strength

wire rope

Boom backstops: Required for all boom lengths



## **Load Hoist System**

Front and rear drums for load hoist powered by a hydraulic variable plunger motors, driven through planetary reducers.

Negative Brake: A spring-set, hydraulically released multipledisc brake is mounted on the hoist motor and operated through a counter-balance valve. (Positive free fall brake is optional item.)

Drum lock: External ratchet for locking drum.

Drums:

#### Front drum:

620 mm P.C.D. x 812 mm Lg. wide drum, grooved for 28 mm wire rope. Rope capacity is 390 m working length and 390 m storage length.

#### Rear drum:

620 mm P.C.D. x 546 mm Lg. wide drum, grooved for 28 mm wire rope. Rope capacity is 220 m working length and 250 m storage length.

Note: Rope lengths listed above denote drum capacity and may differ from actual rope lengths supplied when machinery is shipped.

**Line speed:** Single line on the first drum layer **Hoisting/Lowering:** 110 to 3 m/min

Line Pull:

Rated line pull (Single-line): 132 kN {13.5 tf}



# **Swing System**

Swing unit is powered by hydraulic motor driving spur gears through planetary reducers (2 sets), the swing system provides 360° rotation.

**Swing parking brakes:** A spring-set, hydraulically released multiple-disc brake is mounted on swing motor.

**Swing circle:** Single-row ball bearing with an integral internally cut swing gear.

Swing lock: Manually, four position lock for transportation

Swing speed: 2.2 min<sup>-1</sup> {rpm}



## **Upper Structure**

Torsion-free precision machined upper frame. All components are located clearly and service friendly. Engine with low noise level.

Counterweight: 97.1 ton





# **Cab & Control**

Totally enclosed, full vision cab with safety glass, fully adjustable, high backed seat with a head-rest and armrests, and intermittent wiper and window washer (skylight and front window).

#### Cab fittings:

Air conditioner, convenient compartment (for tool), cup holder, ashtray, cigarette lighter, sun visor, roof blind, tinted glass, floor mat, foot-rest, shoe tray

#### Controls:

Four adjustable levers for front drum, rear drum, boom drum and swing controls



### **Lower Structure**

Steel-welded carbody with axles. Crawler assemblies are designed with quick disconnect feature for individual removal as a unit from axles. Crawler belt tension is maintained by hydraulic jack force on the track-adjusting bearing block.

Carbody weight: 20.0 ton

Crawler drive: Independent hydraulic propel drive is built into each crawler side frame. Each drive consists of a hydraulic motor propelling a driving tumbler through a planetary gear box. Hydraulic motor and gear box are built into the crawler side frame within the shoe width.

**Crawler brakes:** Spring-set, hydraulically released parking brakes are built into each propel drive.

**Steering mechanism:** A hydraulic propel system provides both skid steering (driving one track only) and counter-rotating steering (driving each track in opposite directions).

**Track rollers:** Sealed track rollers for maintenance-free operation.

Shoes (flat): 68 shoes, 1,070 mm wide each crawler

(Optional 1,220 mm shoe is available)

Max. travel speed: 1.1/0.7 km/h Max. gradeability: 30%



#### Weight

Including upper and lower machine, 97.1 ton counterweight and 20.0 ton carbody weight, 15.2 m basic boom (or 36.6 m basic tower + 27.4 m basic tower jib), hook, and other accessories.

SpecificationWeightGround pressureCrane boomApprox. 211 ton, 122 kPa {1.25 kgf/cm²}Tower jibApprox. 220 ton, 128 kPa {1.30 kgf/cm²}



# **Attachment**

#### Boom and Jib:

Welded lattice construction using tubular, high-tensile steel chords with pin connections between sections.

Boom and Jib Length

	Min. Length	Max. Length
	(Min. Combination)	(Max. Combination)
Crane Boom	15.2 m	76.2 m
Long Boom	73.2 m	91.4 m
Fixed Jib	42.7 m + 12.2 m	76.2 m + 30.5 m
Tower Jib	36.6 m + 27.4 m	64.1 m + 51.8 m

## Main Specifications (Model: 7250-2F)

Crane Boom		
Max. Lifting Capacity	250 t/4.6 m	
Max. Length	76.2 m	
Long Boom		
Max. Lifting Capacity	37.5 t/14.4 m	
Max. Length	91.4 m	
Fixed Jib		
Max. Lifting Capacity	22.7 t/15.0 m	
Max. Combination	76.2 m + 30.5 m	
Tower Jib		
Max. Lifting Capacity	25.0 t/18.0 m	
Max. Combination	64.1 m + 51.8 m	
Tower Angle	60° ~ 90°	
Main & Aux. Winch		
Max. Line Speed	110 m/min (1st layer)	
Rated Line Pull (Single Line)	132 kN {13.5 tf}	
Wire Rope Diameter	φ28 mm	
Wire Rope Length	390 m (Main) 220 m (Aux.)	
Brake Type	Spring-set hydraulically released (Negative)	
Free-Fall Brake Type	Wet-type multiple disc brake (Optional)	

2.2 min-1 {rpm}
1.1/0.7 km/h
Hino P11C-UN
247 kW/2,000 min-1 {rpm}
400 liters
4 variable displacement
31.9 MPa {325 kgf/cm²}
600 liters
Approx. 211 t
122 kPa {1.25 kgf/cm²}
97.1 t (Upper), 20.0 t (Lower)
44.5 t

Units are SI units. {} indicates conventional units.


\* Including upper and lower machine, 97.1 ton counterweight and 20.0 ton carbody weight, basic boom, hook, and other accessories.

\*\*Base machine with boom base, carbody, gantry, trans-lifter, lower spreader, upper spreader, main and aux. winches including wire rope, and boom hoist winch including wire rope.




# **GENERAL DIMENSIONS**


Crane Boom (Unit: mm)



# **Limit of Hook Lifting**









# **BOOM AND JIB ARRANGEMENTS**

# **Crane Boom Arrangements**

<b>J</b>		
Boom length m (ft)	Boom arrangement	
15.2 (50)		
18.3 (60)	B 10 T	
21.3 (70)	* S 10101	
24.4 (80)	<b>※</b> ■ 10 20 □	
27.4 (90)	#	
30.5 (100)	* <u>10 20 20 10</u>	
33.5 (110)	*	
36.6 (120)	※ ■ 10 20 40	
39.6 (130)		
42.7 (140)	★ ■ 10   20   20   40   10       ■ 10   40   40   10	
45.7 (150)	*	

Symbol	Boom Length	Remarks	
B	7.6 m	Boom Base	
	7.6 m	Boom Top	
10	3.0 m	Insert Boom	
20	6.1 m	Insert Boom	
40	12.2 m	Insert Boom	

Boom length m (ft)	Boom arrangement
48.8 (160)	* 10 20 40 40 F
51.8 (170)	※     8   10   10   20   40   40   10   10   10   10   10   1
54.9 (180)	#     B     10     20     20     40     40     T
57.9 (190)	**
61.0 (200)	★ ■ 10   20   40   40   10   10   10   10   10   1
64.0 (210)	
67.1 (220)	
70.1 (230)	#
73.2 (240)	★ ■ 10   20   40   40   40   10   10   10   10   1
76.2 (250)	★ ■ 10 10 20 40 40 40 40 17

mark shows the guy line installing position when the fixed jib is used.




# **Long Boom Arrangements**

Boom length m (ft)	Boom arrangement
73.2 (240)	B 40 40 40 TB 10A)T
76.2 (250)	★ B 40 40 40 40 TB 10A 10 T
79.2 (260)	B     40     40     40     TB     10A     10     10     T
82.3 (270)	# E 40 40 40 40 TB 10A 10 20 IT  E 40 40 40 40 TB 10A 30 IT
85.3 (280)	B         10         40         40         40         40         TB         10A         10         20         1         40         40         TB         10A         30         1         40         40         TB         10A         30         1         40 </td
88.4 (290)	B     10     40     40     40     40     TB     10A     10     10     20     T         B     10     40     40     40     40     TB     10A     10     30     T
91.4 (300)	B     10     40     40     40     40     TB     10A     10     10     30     T       B     10     40     40     40     40     TB     10A     20     30     T

Symbol	Long Boom Length	Remarks
В	7.6 m	Boom Base
T 💢	9.1 m	Tower Jib Top
10	3.0 m	Insert Boom
40	12.2 m	Insert Boom
ТВ	4.6 m	Tapered Boom
10A	3.0 m	Relay Jib
10	3.0 m	Tower Insert Jib
20	6.1 m	Tower Insert Jib
30	9.1 m	Tower Insert Jib

<sup>※</sup> Indicates the most flexible combination of insert long booms, which can be modified to form all shorter long boom arrangements.

# **Fixed Jib Arrangements**



Crane boom length	Jib length m (ft)	Jib arrangement
	12.2 (40)	<b>──</b> B 10 T──
42.7 m	18.3 (60)	■ B 10 20 F
76.2 m	24.4 (80)	B 10 20 20 F
	30.5 (100)	──B 10  20   20   7

Jib Length	Remarks
4.6 m	Jib Base
4.6 m	Jib Top
3.0 m	Insert Jib
6.1 m	Insert Jib
	4.6 m 4.6 m 3.0 m



# **Tower Arrangements**

Tower length m (ft)	Tower arrangement
36.6 (120)	Rail for upper spreader of luffing jib
	B 30A 20 40 TW
39.7 (130)	₩ E 30A 10 40 20 TW
42.7 (140)	₩
45.8 (150)	₩ E 30A 10 40 20 20 TW
	B 30A 10 40 40 TW
	※ ■ 30A 10 10 40 20 20 TW
48.8 (160)	B 30A 10 10 40 40 TW
	B 30A 20 40 40 TW

Symbol	Tower Length	Remarks
B	7.6 m	Boom Base
<b>√</b> <sub>TW</sub>	1.6 m	Tower Cap
10	3.0 m	Insert Boom
20	6.1 m	Insert Boom
30A	9.1 m	Special Insert Boom for Tower
40	12.2 m	Insert Boom

Tower length m (ft)	Tower arrangement
51.9 (170)	※ ■ 30A 10 40 20 20 20 TW
	B 30A 10 40 20 40 TW
54.9 (180)	₩ E 30A 10 10 40 20 40 TW
58.0 (190)	★ B 30A 10 40 20 20 40 TW  TW    TW
30.0 (190)	B 30A 10 40 40 TW
	★ B 30A  10 10 40 20 20 40 TW  TW    TW
61.0 (200)	B 30A 10 10 40 40 40 TW
	B 30A 20 40 40 TW
64.1 (010)	₩ = B 30A 10 40 20 20 20 40 TW
64.1 (210)	B 30A 10 40 20 40 40 TW

 $<sup>\</sup>ensuremath{\ensuremath{\%}}$  Indicates the most flexible combination of insert towers, which can be modified to form all shorter tower arrangements.



# **Tower Jib Arrangements**

	•
Jib length m (ft)	Jib arrangement
27.4 (90)	JB 10A 20 JT
00 F (100)	
30.5 (100)	
00 F (440)	
33.5 (110)	
36.6 (120)	
36.6 (120)	
20.6 (120)	
39.6 (130)	

Jib length m (ft)	Jib arrangement
42.7 (140)	
42.7 (140)	<u>JB 10A 10 10 30 130 JJT</u> →
45.7 (450)	
45.7 (150)	
48.8 (160)	<sup>3</sup> 30 1 30 30 30 30 30 30 30 30 30 30 30 30 30
51.8 (170)	※

Symbol	Tower Jib Length	Remarks				
JB	9.1 m	Tower Jib Base				
JT	9.1 m	Tower Jib Top				
10A	3.0 m	Relay Jib				
10	3.0 m	Tower Insert Jib				
20	6.1 m	Tower Insert Jib				
30	9.1 m	Tower Insert Jib				

# **Tower and Jib Combinations and Allowable Tower Angle**

Towe	Jib length	27.4m	30.5m	33.5m	36.6m	39.6m	42.7m	45.7m	48.8m	51.8m	Pillow plate
	36.6m	90°-60°	90°-60°	_	_	_	_	_	_	_	_
	39.7m	90°-60°	90°-60°	90°-60°	_	_	_	_	_	_	_
	42.7m	90°-60°	90°-60°	90°-60°	90°-60°	_	_	_	_	_	_
	45.8m	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	-	_	_	_	_
	48.8m	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	_	_	_	_
	51.9m	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	_	_	_
	54.9m	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	1	_
	58.0m	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	90°-70°	_
	61.0m	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	90°-70°	_
	64.1m	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	90°-60°	90°-70°	90°-70°	90°-70°	Need
송	35 ton hook	0	0	0	0	0	0	0	0	0	
운	35 ton hook Ball hook	×	0	0	0	0	0	0	0	0	

Indicates the most flexible combination of insert tower jibs, which can be modified to form all shorter tower jib arrangements.
 mark: indicates position where cable rollers attached.





# **Hook Blocks**

A range of hook blocks can be specified, each with a safety latch.

U					•									
Llaa	Hooks	Weight (kg)	No. of	No. of lines and max. rated loads (tons)										
ПОО			sheaves	1	2	3	4	5	6	7	8			
250-	ton	4,200	11	•	-	-	54.0	-	81.0	-	108.0			
150-	ton	2,300	6	-	-	40.5	54.0	67.5	81.0	94.5	108.0			
70-1	ton	1,200	3	-	27.0	40.5	54.0	67.5	70.0	-	-			
35-1	ton	900	1	-	27.0	35.0	-	-	-	-	-			
13.5- ball h		450	0	13.5	-	-	-	-	-	-	-			


Hooks	Weight (kg)	No. of	No. of No. of lines and max. rated loads (tons)									
		sheaves	9	10	12	14	16	18	20	22		
250-ton	4,200	11	-	135.0	156.0	182.0	200.0	225.0	240.0	250.0		
150-ton	2,300	6	121.5	135.0	150.0	-	-	-	-	-		
70-ton	1,200	3	-	-	-	•	-	-	-	-		
35-ton	900	1	-	-	-	•	-	-	-	-		
13.5-ton ball hook	450	0	-	-	-	-	-	-	-	-		

# Style and Combination of Boom and Jib

	Style	Crane Boom	Long Boom	Fixed Jib	Tower Jib
	7.6 m boom base	Common use(1)	Common use(1)	Common use(1)	Common use(1)
om/Tower	7.6 m boom top	Common use(1)	N.A.	Common use(1)	N.A.
Ę	1.6 m tower cap	N.A.	N.A.	N.A.	Luffing Tower only(1)
È	3.0 m insert boom	Common use(2)	Common use(1)	Common use(2)	Common use(1)
Bo	6.1 m insert boom	Common use(1)	N.A.	Common use(1)	Common use(3)
ne	12.2 m insert boom	Common use(4)	Common use(4)	Common use(4)	Common use(2)
Cra	9.1 m special insert boom for tower	N.A.	N.A.	N.A.	Luffing Tower only(1)
	4.6 m tapered boom	N.A.	Long Boom only(1)	N.A.	N.A.
	4.6 m jib base	N.A.	N.A.	Fixed Jib only(1)	N.A.
	4.6 m jib top	N.A.	N.A.	Fixed Jib only(1)	N.A.
g	3.0 m insert jib	N.A.	N.A.	Fixed Jib only(1)	N.A.
Wer	6.1 m insert jib	N.A.	N.A.	Fixed Jib only(3)	N.A.
Jib/Tower	9.1 m tower jib base	N.A.	N.A.	N.A.	Luffing Tower only(1)
dib	9.1 m tower jib top	N.A.	Common use(1)	N.A.	Common use(1)
Fixed	3.0 m relay jib	N.A.	Common use(1)	N.A.	Common use(1)
ιĚ	3.0 m tower insert jib	N.A.	Common use(2)	N.A.	Common use(2)
	6.1 m tower insert jib	N.A.	Common use	N.A.	Common use(1)
	9.1 m tower insert jib	N.A.	Common use(1)	N.A.	Common use(2)

1. Figure in ( ) means the numbers of the maximum usable boom (or jib) respectively. 2. N.A.: Not applicable

# **Symbols for Attachments:**








# WORKING RANGES AND LIFTING CAPACITIES

# **Crane Boom Working Ranges**



#### NOTES:

- Ratings according to Japanese Construction Codes for Mobile Cranes and Japanese Safety Ordinance on Cranes, etc.
- 2. Ratings in metric tons for 360° working area.
- 3. Operating radius is the horizontal distance from center of rotation to a vertical line through the center of gravity of the load.
- 4. Weight of hook block(s), slings and other load handling accessories is included in rated load. Their total weight must be subtracted from rated load to obtain weight that can be lifted.
- 5. Ratings shown are based on freely suspended loads and make no allowance for such factors as wind effect on lifted load, ground conditions out-of-level, operating speeds or any other condition that could be detrimental to the safe operation of this equipment. Operator, therefore, has the responsibility to judge the existing conditions and reduce lifted loads and operating speeds accordingly.
- 6. Ratings are for operation on a firm and level surface.
- At radii and boom lengths where no ratings are shown on chart, operation is not intended nor approved.

- 8. Boom inserts and guy lines must be arranged as shown in the "Operator's Manual".
- 9. Boom hoist reeving is 16 part line.
- 10. Gantry must be in raised position for all conditions.
- 11. Boom backstops are required for all boom lengths.
- Ratings shown in \_\_\_\_\_ are determined by the strength of the boom or other structural component.
- 13. Instruction in the "Operator's Manual" must be strictly observed when operating the machine.
- 14. Crane boom ratings: Deduct weight of main hook block, slings, and all other load handling accessories from crane boom ratings shown.
- 15. Auxiliary sheave ratings for crane boom: Deduct weight of ball hook, slings, and all other load handling accessories from auxiliary sheave ratings for crane boom shown.
- 16. Crane boom lengths for auxiliary sheave mounting are 15.2 m to 76.2 m.
- 17. Crane boom ratings with auxiliary sheave: Deduct 0.9 ton from crane boom ratings shown. Minimum rated loads must exceed 2.4 ton.





# **Crane Boom Lifting Capacity**

Unit: metric ton

cran	e Bo	om L	LITTIN	IO Ca	abac	ITV						OII	it. Illetile toll
				9 -		J		С	ounterwe	eight: 97.	1 t, Carbo	dy weigh	nt: 20.0 t
Boom length Working (m) radius (m)	15.2	18.3	21.3	24.4	27.4	30.5	33.5	36.6	39.6	42.7	45.7	48.8	Boom length (m) Working radius (m
4.6	4.6 m/250.0												4.6
5.0	230.7	219.0	5.5 m/197.6										5.0
6.0	191.5	191.5	191.1	6.1 m/175.6	6.6 m/156.0								6.0
7.0	165.9	165.6	165.2	165.0	154.4	7.1 m/135.0	7.7m/128.5						7.0
8.0	146.1	145.8	145.4	145.2	144.9	135.0	127.0	8.2 m/117.3	8.7m/107.1				8.0
9.0	130.4	130.1	129.8	129.6	129.2	129.0	122.9	114.4	106.2	9.2 m/98.6	9.8 m/90.4		9.0
10.0	117.7	117.4	117.1	116.9	116.5	116.3	116.0	111.2	103.3	96.6	89.9	10.3 m/81.0	10.0
12.0	90.5	90.3	90.1	90.0	89.8	89.8	89.5	89.5	89.4	89.2	85.1	79.8	12.0
14.0	69.0	72.7	72.4	72.3	72.1	72.0	71.8	71.8	71.6	71.4	71.2	71.2	14.0
16.0	14.8 m/60.9	60.6	60.3	60.2	60.0	59.9	59.6	59.6	59.4	59.2	59.0	59.0	16.0
18.0		17.5 m/52.2	51.6	51.4	51.2	51.1	50.8	50.8	50.5	50.3	50.1	50.1	18.0
20.0			45.0	44.8	44.5	44.4	44.0	44.0	43.8	43.6	43.4	43.3	20.0
22.0			20.1 m/44.8	39.6	39.3	39.1	38.8	38.8	38.5	38.3	38.1	38.0	22.0
24.0				22.7 m/38.0	35.1	34.9	34.5	34.5	34.2	34.0	33.8	33.7	24.0
26.0					25.4 m/32.6	31.4	31.0	31.0	30.7	30.5	30.3	30.2	26.0
28.0						28.5	28.1	28.1	27.8	27.5	27.3	27.3	28.0
30.0							25.7	25.7	25.3	25.1	24.8	24.8	30.0
32.0							30.7 m/25.0	23.5	23.2	22.9	22.7	22.6	32.0
34.0								33.3 m/22.3	21.4	21.1	20.8	20.7	34.0
36.0									35.9 m/19.8	19.5	19.2	19.1	36.0
38.0										18.1	17.8	17.7	38.0
40.0										38.6 m/17.7	16.5	16.4	40.0
42.0											41.2 m/15.8	15.3	42.0
44.0												43.9 m/14.3	44.0
Reeves	22	18	16	14	12	10	10	9	8	8	7	6	Reeves

Boom length Working (m) radius (m)	51.8	54.9	57.9	61.0	64.0	67.1	70.1	73.2	76.2	Boom length (m) Working radius (m)
10.0	10.8 m/77.0	11.4 m/71.4	11.9m/65.8							10.0
12.0	75.0	70.4	65.6	12.4 m/61.1	12.9 m/56.3	13.5 m/51.6				12.0
14.0	70.8	66.5	61.9	58.3	54.7	50.8	47.6	14.5 m/43.1	15.1 m/37.1	14.0
16.0	58.7	58.5	58.4	55.2	51.6	48.0	44.9	41.4	35.9	16.0
18.0	49.8	49.6	49.5	49.3	48.7	45.3	42.3	38.9	33.8	18.0
20.0	43.1	42.8	42.7	42.6	42.3	42.2	39.8	36.7	31.8	20.0
22.0	37.7	37.5	37.4	37.2	37.0	36.9	36.6	34.5	29.8	22.0
24.0	33.5	33.2	33.1	32.9	32.6	32.6	32.3	32.1	27.9	24.0
26.0	29.9	29.7	29.5	29.4	29.1	29.0	28.8	28.6	26.2	26.0
28.0	27.0	26.7	26.6	26.4	26.1	26.0	25.8	25.6	24.5	28.0
30.0	24.5	24.2	24.0	23.9	23.6	23.5	23.2	23.1	23.0	30.0
32.0	22.3	22.1	21.9	21.7	21.4	21.3	21.1	20.9	20.8	32.0
34.0	20.4	20.2	20.0	19.8	19.6	19.5	19.2	19.0	18.9	34.0
36.0	18.8	18.5	18.4	18.2	17.9	17.8	17.5	17.3	17.2	36.0
38.0	17.4	17.1	16.9	16.7	16.4	16.3	16.0	15.9	15.8	38.0
40.0	16.1	15.8	15.6	15.4	15.1	15.0	14.7	14.6	14.5	40.0
42.0	14.9	14.7	14.5	14.3	14.0	13.9	13.6	13.4	13.3	42.0
44.0	13.9	13.7	13.4	13.3	12.9	12.8	12.5	12.4	12.2	44.0
46.0	13.0	12.7	12.5	12.3	12.0	11.9	11.6	11.4	11.3	46.0
48.0	46.5 m/12.8	11.9	11.6	11.5	11.2	11.0	10.7	10.6	10.4	48.0
50.0		49.1 m/11.5	10.9	10.7	10.4	10.2	9.9	9.8	9.6	50.0
52.0			51.8 m/10.3	10.0	9.7	9.5	9.2	9.0	8.9	52.0
54.0				9.4	9.0	8.9	8.6	8.4	8.2	54.0
56.0				54.4 m/9.2	8.4	8.3	8.0	7.8	7.6	56.0
58.0					57.1m/8.2	7.7	7.4	7.2	6.9	58.0
60.0						59.7 m/7.3	6.8	6.6	6.3	60.0
62.0							6.3	6.0	5.7	62.0
64.0							62.3 m/6.2	5.5	5.2	64.0
66.0								65.0 m/5.3	4.7	66.0
68.0									67.6 m/4.3	68.0
Reeves	6	6	5	5	5	4	4	4	3	Reeves

Note

Ratings according to Japanese Construction Codes for Mobile Cranes and Japanese Safety Ordinance on Cranes, etc.

Ratings shown in \_\_\_\_\_ are determined by the strength of the boom or other structural components.

Refer to notes P12.







# Auxiliary Sheave Lifting Capacity for Crane Boom Onit: metric ton Counterweight: 97.1 t, Carbody weight: 20.0 t

(Anici	1 / 0	LIVIG		COR	countermolymatically molymatical								
Boom length Working (m) radius (m)	15.2	18.3	21.3	24.4	27.4	30.5	33.5	36.6	39.6	42.7	45.7	48.8	Boom length (m) Working radius (m)
5.0	5.4 m/13.5	5.8 m/13.5											5.0
6.0	13.5	13.5	6.3 m/13.5	6.9 m/13.5									6.0
7.0	13.5	13.5	13.5	13.5	7.4 m/13.5	7.9 m/13.5							7.0
8.0	13.5	13.5	13.5	13.5	13.5	13.5	8.5 m/13.5						8.0
9.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	9.5 m/13.5				9.0
10.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	10.6 m/13.5	11.1 m/13.5	10.0
12.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	12.0
14.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	14.0
16.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	16.0
18.0	16.1 m/13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	18.0
20.0		18.8 m/13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	20.0
22.0			21.4 m/13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	22.0
24.0				13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	24.0
26.0					13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	26.0
28.0					26.7 m/13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	28.0
30.0						29.3 m/13.5	13.5	13.5	13.5	13.5	13.5	13.5	30.0
32.0							13.5	13.5	13.5	13.5	13.5	13.5	32.0
34.0								13.5	13.5	13.5	13.5	13.5	34.0
36.0								34.6 m/13.5	13.5	13.5	13.5	13.5	36.0
38.0									37.2 m/13.5	13.5	13.5	13.5	38.0
40.0										39.9 m/13.5	13.5	13.5	40.0
42.0											13.5	13.5	42.0
44.0											42.5m/13.4	12.7	44.0
46.0												45.2 m/12.0	46.0
Reeves	1	1	1	1	1	1	1	1	1	1	1	1	Reeves

Boom length Working (m) radius (m)	51.8	54.9	57.9	61.0	64.0	67.1	70.1	73.2	76.2	Boom length (m) Working radius (m)
10.0	11.6 m/13.5									10.0
12.0	13.5	12.2 m/13.5	12.7 m/13.5	13.2 m/13.5	13.7 m/13.5					12.0
14.0	13.5	13.5	13.5	13.5	13.5	14.3 m/13.5	14.8 m/13.5	15.3 m/13.5	15.9 m/13.5	14.0
16.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	16.0
18.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	18.0
20.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	20.0
22.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	22.0
24.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	24.0
26.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	26.0
28.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	28.0
30.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	30.0
32.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	32.0
34.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	34.0
36.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	36.0
38.0	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	13.5	38.0
40.0	13.5	13.5	13.5	13.5	13.5	13.5	13.2	13.1	13.0	40.0
42.0	13.4	13.2	13.0	12.8	12.5	12.4	12.1	11.9	11.8	42.0
44.0	12.4	12.2	11.9	11.8	11.4	11.3	11.0	10.9	10.7	44.0
46.0	11.5	11.2	11.0	10.8	10.5	10.4	10.1	9.9	9.8	46.0
48.0	47.8 m/10.7	10.4	10.1	10.0	9.7	9.5	9.2	9.1	8.9	48.0
50.0		9.6	9.4	9.2	8.9	8.7	8.4	8.3	8.1	50.0
52.0		50.4 m/9.4	8.7	8.5	8.2	8.0	7.7	7.5	7.4	52.0
54.0			53.1 m/8.3	7.9	7.5	7.4	7.1	6.9	6.7	54.0
56.0				55.7 m/7.4	6.9	6.8	6.5	6.3	6.1	56.0
58.0					6.3	6.2	5.9	5.7	5.4	58.0
60.0					58.4 m/6.2	5.6	5.3	5.1	4.8	60.0
62.0						61.0 m/5.3	4.8	4.5	4.2	62.0
64.0							63.6 m/4.4	4.0	3.7	64.0
66.0								3.5	3.2	66.0
68.0								66.3 m/3.4	2.7	68.0
70.0									68.9 m/2.5	70.0
Reeves	1	1	1	1	1	1	1	1	1	Reeves


Ratings according to Japanese Construction Codes for Mobile Cranes and Japanese Safety Ordinance on Cranes, etc.

Ratings shown in \_\_\_\_\_\_ are determined by the strength of the boom or other structural components.

Refer to notes P12.

# 3

# **Long Boom Working Ranges**



#### NOTES

- Ratings according to Japanese Construction Codes for Mobile Cranes and Japanese Safety Ordinance on Cranes, etc.
- 2. Ratings in metric tons for 360° working area.
- Operating radius is the horizontal distance from center of rotation to a vertical line through the center of gravity of the load.
- Weight of hook block(s), slings and other load handling accessories is included in rated load. Their total weight must be subtracted from rated load to obtain weight that can be lifted.
- 5. Ratings shown are based on freely suspended loads and make no allowance for such factors as wind effect on lifted load, ground conditions out-of-level, operating speeds or any other condition that could be detrimental to the safe operation of this equipment. Operator, therefore, has the responsibility to judge the existing conditions and reduce lifted loads and operating speeds accordingly.
- $\ensuremath{\mathsf{6}}.$  Ratings are for operation on a firm and level surface.
- At radii and boom lengths where no ratings are shown on chart, operation is not intended nor approved.

- 8. Boom inserts and guy lines must be arranged as shown in the "Operator's Manual".
- Gantry must be in raised position for all conditions.
- 10. Boom backstops are required for all boom lengths.
- 11. Ratings shown in \_\_\_\_\_ are determined by the strength of the boom or other structural component.
- 12. Instruction in the "Operator's Manual" must be strictly observed when operating the machine.
- Long boom ratings: Deduct weight of hook block, slings, and all other load handling accessories from long boom ratings shown.
- 14. Auxiliary sheave ratings for long boom: Deduct weight of ball hook, slings, and all other load handling accessories from auxiliary sheave ratings for long boom shown.
- 15. Long boom lengths for auxiliary sheave mounting are 73.2 m to 88.4 m.
- Long boom ratings with auxiliary sheave: Deduct 0.9 ton from long boom ratings shown. Minimum rated loads must exceed 2.4 ton.





# **Long Boom Lifting Capacity**

Boom length Working (m) radius (m)	73.2	76.2	79.2	82.3	85.3	88.4	91.4	Boom length (m) Working radius (m)
14.0	14.4 m/37.5	14.9 m/34.5	15.4 m/32.6					14.0
16.0	36.0	33.5	32.1	31.2	16.5 m/25.0	17.0 m/25.0	17.6 m/21.5	16.0
18.0	34.4	31.9	30.6	29.6	25.0	25.0	21.2	18.0
20.0	32.9	30.4	29.1	28.2	25.0	24.1	20.0	20.0
22.0	31.6	29.1	27.9	26.9	25.0	23.0	18.9	22.0
24.0	30.4	27.9	26.8	25.7	24.2	22.0	17.8	24.0
26.0	28.8	26.5	25.6	24.6	23.2	21.1	16.9	26.0
28.0	26.2	25.2	24.5	23.6	22.3	20.1	16.0	28.0
30.0	23.8	23.6	23.3	22.6	21.1	19.1	15.3	30.0
32.0	21.8	21.7	21.6	21.5	19.9	18.1	14.5	32.0
34.0	19.9	19.9	19.7	19.7	18.7	17.1	13.8	34.0
36.0	18.3	18.3	18.2	18.1	17.7	16.1	13.1	36.0
38.0	16.9	16.8	16.7	16.7	16.5	15.1	12.5	38.0
40.0	15.6	15.6	15.4	15.4	15.4	14.2	11.8	40.0
42.0	14.5	14.5	14.3	14.3	14.3	13.4	11.2	42.0
44.0	13.4	13.4	13.2	13.2	13.2	12.5	10.7	44.0
46.0	12.5	12.5	12.3	12.3	12.2	11.8	10.2	46.0
48.0	11.6	11.5	11.4	11.4	11.3	11.1	9.8	48.0
50.0	10.7	10.7	10.6	10.5	10.5	10.3	9.4	50.0
52.0	10.0	10.0	9.9	9.8	9.8	9.6	8.9	52.0
54.0	9.3	9.3	9.1	9.1	9.0	9.0	8.5	54.0
56.0	8.6	8.6	8.5	8.4	8.4	8.4	7.8	56.0
58.0	8.0	8.0	7.8	7.8	7.7	7.7	7.2	58.0
60.0	7.4	7.3	7.2	7.2	7.1	7.1	6.7	60.0
62.0	6.8	6.7	6.7	6.6	6.6	6.6	6.1	62.0
64.0	6.3	6.1	6.1	6.1	6.0	6.0	5.6	64.0
66.0	64.9 m/6.1	5.6	5.6	5.6	5.6	5.6	5.1	66.0
68.0		67.5 m/5.4	5.3	5.2	5.2	5.2	4.6	68.0
70.0			4.8	4.7	4.7	4.7	4.1	70.0
72.0			70.2 m/4.8	4.3	4.3	4.3	3.6	72.0
74.0				72.8 m/4.2	3.9	3.9	3.1	74.0
76.0					74.5 m/3.7	3.5	2.6	76.0
78.0						3.2		78.0
80.0						78.1 m/3.2		80.0
Reeves	3	3	3	3	2	2	2	Reeves

Unit: metric ton

Counterweight: 97.1 t,

Carbody weight: 20.0 t

Note:
Ratings according to Japanese
Construction Codes for Mobile Cranes and
Japanese Safety Ordinance on Cranes,
etc.
Ratings shown in \_\_\_\_\_\_ are determined
by the strength of the boom or other struc-

tural components.

**Auxiliary Sheave Lifting Capacity for Long Boom (Without Main Hook)** 

Boom length Working (m) radius (m)	73.2	76.2	79.2	82.3	85.3	88.4	Boom length (m) Working radius (m)
14.0	15.1 m/13.5	15.7 m/13.5					14.0
16.0	13.5	13.5	16.2 m/13.5	16.7 m/13.5	17.3 m/13.5	17.8 m/13.5	16.0
18.0	13.5	13.5	13.5	13.5	13.5	13.5	18.0
20.0	13.5	13.5	13.5	13.5	13.5	13.5	20.0
22.0	13.5	13.5	13.5	13.5	13.5	13.5	22.0
24.0	13.5	13.5	13.5	13.5	13.5	13.5	24.0
26.0	13.5	13.5	13.5	13.5	13.5	13.5	26.0
28.0	13.5	13.5	13.5	13.5	13.5	13.5	28.0
30.0	13.5	13.5	13.5	13.5	13.5	13.5	30.0
32.0	13.5	13.5	13.5	13.5	13.5	13.5	32.0
34.0	13.5	13.5	13.5	13.5	13.5	13.5	34.0
36.0	13.5	13.5	13.5	13.5	13.5	13.5	36.0
38.0	13.5	13.5	13.5	13.5	13.5	13.5	38.0
40.0	13.5	13.5	13.5	13.5	13.5	13.5	40.0
42.0	13.5	13.5	13.5	13.5	13.5	13.1	42.0
44.0	13.1	13.1	12.9	12.9	12.9	12.2	44.0
46.0	12.2	12.2	12.0	12.0	11.9	11.5	46.0
48.0	11.3	11.2	11.1	11.1	11.0	10.8	48.0
50.0	10.4	10.4	10.3	10.2	10.2	10.0	50.0
52.0	9.7	9.7	9.6	9.5	9.5	9.3	52.0
54.0	9.0	9.0	8.8	8.8	8.7	8.7	54.0
56.0	8.3	8.3	8.2	8.1	8.1	8.1	56.0
58.0	7.7	7.7	7.5	7.5	7.4	7.4	58.0
60.0	7.1	7.0	6.9	6.9	6.8	6.8	60.0
62.0	6.5	6.4	6.4	6.3	6.3	6.3	62.0
64.0	6.0	5.8	5.8	5.8	5.7	5.7	64.0
66.0	5.5	5.3	5.3	5.3	5.3	5.3	66.0
68.0		4.8	5.0	4.9	4.9	4.9	68.0
70.0		68.7 m/4.6	4.5	4.4	4.4	4.4	70.0
72.0			71.3 m/4.2	4.0	4.0	4.0	72.0
74.0				3.6	3.6	3.6	74.0
76.0					3.2	3.2	76.0
78.0					76.6 m/3.1	2.9	78.0
Reeves	1	1	1	1	1	1	Reeves

Unit: metric ton

Counterweight: 97.1 t,

Carbody weight: 20.0 t


Note:

Ratings according to Japanese Construction Codes for Mobile Cranes and Japanese Safety Ordinance on Cranes, etc.

Ratings shown in \_\_\_\_\_ are determined by the strength of the boom or other structural components. Refer to notes P15.



# **Fixed Jib Working Ranges**



# NOTES:

- Ratings according to Japanese Construction Codes for Mobile Cranes and Japanese Safety Ordinance on Cranes, etc.
- 2. Ratings in metric tons for 360° working area.
- 3. Operating radius is the horizontal distance from center of rotation to a vertical line through the center of gravity of the load.
- Weight of hook block(s), slings and other load handling accessories is included in rated load. Their total weight must be subtracted from rated load to obtain weight that can be lifted.
- 5. Ratings shown are based on freely suspended loads and make no allowance for such factors as wind effect on lifted load, ground conditions out-of-level, operating speeds or any other condition that could be detrimental to the safe operation of this equipment. Operator, therefore, has the responsibility to judge the existing conditions and reduce lifted loads and operating speeds accordingly.
- 6. Ratings are for operation on a firm and level surface.

- At radii and boom lengths where no ratings are shown on chart, operation is not intended nor approved.
- 8. Boom/ jib inserts and guy lines must be arranged as shown in the "Operator's Manual".
- 9. Gantry must be in raised position for all conditions.
- 10. Boom backstops are required for all boom lengths.
- 11. Ratings shown in \_\_\_\_\_ are determined by the strength of the boom or other structural component.
- 12. When erecting or lowering the boom length of 76.2 m, the pillow plate for erection must be placed at the end of crawlers.
- 13. Instruction in the "Operator's Manual" must be strictly observed when operating the machine.
- 14. Fixed jib ratings: Deduct weight of jib hook block, slings, and all other load handling accessories from fixed jib ratings shown.
- 15. Crane boom lengths for fixed jib mounting are 42.7 m to 76.2 m.
- 16. One part of line on hook is not allowed to use for 12.2 m jib length with offset angle 10 degrees.





# **Fixed Jib Lifting Capacities (Without Main Hook)**

Unit: metric ton

Jib Offset Angle: 10°

Counterweight: 97.1 t, Carbody weight: 20.0 t

			9											J	, 00			
Boor	n length (m)		42	2.7			48	3.8			54	1.9			61.0		Boom lengti	(m)
Jib	length (m)	12.2	18.3	24.4	30.5	12.2	18.3	24.4	30.5	12.2	18.3	24.4	30.5	18.3	24.4	30.5	Jib length	n)
	12.0	12.9 m/22.7				13.9 m/22.7											12.0	Т
	14.0	22.4	15.3 m/15.3			22.7				15.0 m/22.7							14.0	
	16.0	22.0	15.1	17.1 m/8.6		22.2	16.3 m/15.2			22.5	17.4 m/13.5						16.0	
	18.0	21.6	14.8	8.5	18.5 m/5.1	21.8	15.0	18.1 m/8.5	19.6 m/5.1	22.1	13.5	19.2 m/8.5		18.4 m/13.5			18.0	
	20.0	21.1	14.6	8.3	5.0	21.4	14.7	8.4	5.0	21.7	13.5	8.5	20.6 m/5.0	13.5	20.3 m/8.5	21.7 m/5.0	20.0	
	22.0	20.8	14.3	8.2	4.9	21.1	14.5	8.3	4.9	21.4	13.5	8.3	5.0	13.5	8.4	5.0	22.0	
	24.0	20.4	14.0	8.1	4.8	20.7	14.2	8.2	4.8	21.0	13.5	8.2	4.9	13.5	8.3	4.9	24.0	
	26.0	20.1	13.8	7.8	4.6	20.4	14.0	8.0	4.7	20.7	13.5	8.1	4.8	13.5	8.2	4.8	26.0	
	28.0	19.8	13.5	7.5	4.4	20.1	13.7	7.8	4.5	20.4	13.5	8.0	4.7	13.5	8.1	4.8	28.0	<
s (m)	30.0	19.5	13.3	7.3	4.2	19.9	13.5	7.5	4.4	20.2	13.5	7.7	4.5	13.5	7.9	4.6	30.0	ş
radius	34.0	18.8	12.9	6.8	3.9	19.1	13.1	7.1	4.0	19.7	13.3	7.3	4.2	13.5	7.5	4.3	34.0	g
ng	38.0	17.4	11.9	6.5	3.6	17.8	12.8	6.7	3.8	17.4	13.0	6.9	3.9	13.2	7.1	4.0	38.0	radii
Working	42.0	15.8	10.9	6.1	3.4	15.5	11.7	6.4	3.5	14.9	12.6	6.6	3.7	12.9	6.8	3.8	42.0	Working radius (m)
>	46.0	14.0	10.0	5.9	3.2	13.4	10.8	6.1	3.3	12.8	11.6	6.3	3.5	12.3	6.5	3.6	46.0	ತ
	50.0	12.2	9.3	5.6	3.0	11.7	10.0	5.8	3.2	11.1	10.7	6.0	3.3	11.1	6.2	3.4	50.0	
	54.0	50.3 m/12.1	8.7	5.4	2.9	10.3	9.4	5.6	3.0	9.7	10.0	5.8	3.1	9.6	6.0	3.2	54.0	
	58.0		56.1 m/8.4	5.3	2.7	55.5 m/9.8	8.8	5.4	2.9	8.5	8.9	5.6	3.0	8.4	5.8	3.1	58.0	
	62.0			61.7 m/5.1	2.6		61.4 m/8.4	5.3	2.7	60.8 m/7.8	7.8	5.4	2.8	7.3	5.6	3.0	62.0	
	66.0				2.5			5.2	2.6		6.9	5.3	2.7	6.4	5.4	2.8	66.0	
	70.0				67.2 m/2.5			67.0m/5.1	2.6		66.6 m/6.8	5.2	2.6	5.6	5.3	2.7	70.0	
	74.0								72.5 m/2.5			72.3 m/5.1	2.6	71.9 m/5.2	5.2	2.6	74.0	
	78.0												77.7 m/2.5		77.6 m/4.7	2.6	78.0	
	82.0															2.5	82.0	
	84.0															83.0 m/2.5	84.0	
Re	eeves	2	2	1	1	2	2	1	1	2	1	1	1	1	1	1	Reeve	3

Booi	m length (m)		67.1			73.2			76.2		Boom lengt	:h (m)
Jib	length (m)	18.3	24.4	30.5	18.3	24.4	30.5	18.3	24.4	30.5	Jib length	(m)
	16.0										16.0	
	18.0	19.4 m/13.5									18.0	1
	20.0	13.5	21.4 m/8.5		20.5 m/13.5			21.1 m/13.5			20.0	
	22.0	13.5	8.5	22.7 m/5.0	13.5	22.3 m/8.5	23.8 m/5.0	13.5	22.9 m/8.5		22.0	1
	24.0	13.5	8.3	5.0	13.5	8.4	5.0	13.5	8.4	24.4 m/5.0	24.0	
	26.0	13.5	8.2	4.9	13.5	8.3	4.9	13.5	8.3	4.9	26.0	
	28.0	13.5	8.1	4.8	13.5	8.2	4.8	13.5	8.2	4.8	28.0	
	30.0	13.5	8.1	4.7	13.5	8.1	4.8	13.5	8.1	4.8	30.0	
Ê	34.0	13.5	7.7	4.4	13.5	7.8	4.5	13.5	7.9	4.6	34.0	8
Working radius (m)	38.0	13.3	7.3	4.2	13.5	7.5	4.3	13.5	7.5	4.3	38.0	Working radius (m)
rad	42.0	13.0	7.0	3.9	13.2	7.1	4.0	13.3	7.2	4.1	42.0	gra
king	46.0	12.2	6.7	3.7	11.7	6.8	3.8	11.4	6.9	3.9	46.0	dius
Worl	50.0	10.5	6.4	3.5	10.0	6.6	3.6	9.7	6.7	3.7	50.0	3
-	54.0	9.0	6.2	3.3	8.5	6.3	3.5	8.2	6.4	3.5	54.0	]
	58.0	7.8	6.0	3.2	7.3	6.1	3.3	7.0	6.2	3.3	58.0	
	62.0	6.7	5.8	3.1	6.2	5.9	3.2	5.9	6.0	3.2	62.0	1
	66.0	5.8	5.6	2.9	5.3	5.7	3.0	5.0	5.5	3.1	66.0	
	70.0	5.0	5.4	2.8	4.5	5.0	2.9	4.1	4.7	3.0	70.0	
	74.0	4.3	4.7	2.7	3.7	4.3	2.8	3.4	4.0	2.9	74.0	
	78.0	77.2 m/3.8	4.1	2.6	3.1	3.6	2.7	2.8	3.3	2.8	78.0	
	82.0		3.5	2.6	2.5	3.0	2.6	80.0 m/2.5	2.7	2.7	82.0	
	86.0		82.8 m/3.3	2.5		2.5	2.6		84.0 m/2.4	2.5	86.0	
	90.0			88.3 m/2.5			88.0 m/2.4				90.0	
R	eeves	1	1	1	1	1	1	1	1	1	Reeve	<b>?</b> S

Note:

Ratings according to Japanese Construction Codes for Mobile Cranes and Japanese Safety Ordinance on Cranes, etc.
Ratings shown in \_\_\_\_\_\_ are determined by the strength of the boom or other structural components.

Refer to notes P17.

※1 One part of line on hook is not allowed to use for 12.2 m jib length with offset angle 10 degrees.
※2 Crane boom lengths for 12.2 m fixed jib with offset angle 10 degrees mounting are 42.7 m to 57.9 m.



# Jib Offset Angle: 30°

Unit: metric ton

IL	וט כ	ISEL	Ang	le: 3	U							Cou	nterwei	ght: 97	.1 t, Ca	rbody	weight	: 20.0	t
Boon	n length (m)		42	2.7			48	3.8			54	1.9			61	.0		Boom leng	jth (r
Jib	length (m)	12.2	18.3	24.4	30.5	12.2	18.3	24.4	30.5	12.2	18.3	24.4	30.5	12.2	18.3	24.4	30.5	Jib length	n (m
	16.0	16.5 m/18.4				17.6 m/18.4												16.0	Τ
Ī	18.0	17.7				18.2				18.7 m/18.4				19.8 m/13.5				18.0	1
ı	20.0	16.8	20.7 m/12.1			17.3	21.7 m/12.1			17.8				13.5				20.0	1
Ī	22.0	16.0	11.8			16.6	12.1			17.1	22.8 m/12.1			13.5	23.9 m/12.1			22.0	1
ı	24.0	15.3	11.3	24.4 m/6.3		15.9	11.6	25.4 m/6.3		16.4	11.9			13.5	12.1			24.0	1
Ī	26.0	14.7	10.7	6.2	27.7 m/3.3	15.2	11.1	6.2		15.7	11.4	26.5 m/6.2		13.5	11.7	27.6 m/6.2		26.0	1
Ī	28.0	14.1	10.3	6.0	3.3	14.7	10.6	6.1	28.8 m/3.3	15.2	11.0	6.2	29.9 m/3.3	13.5	11.3	6.2		28.0	1
Ē	30.0	13.6	9.9	5.9	3.2	14.1	10.2	6.0	3.2	14.7	10.6	6.0	3.3	13.5	10.9	6.1	30.9 m/3.3	30.0	1
radius (m)	34.0	12.7	9.2	5.6	3.0	13.2	9.5	5.7	3.1	13.8	9.9	5.8	3.1	13.5	10.2	5.9	3.2	34.0	1
9	38.0	12.0	8.6	5.4	2.9	12.5	8.9	5.5	2.9	13.0	9.3	5.6	3.0	13.4	9.6	5.7	3.0	38.0	1
1	42.0	11.4	8.1	5.2	2.8	11.9	8.4	5.4	2.8	12.4	8.7	5.5	2.9	12.8	9.0	5.5	2.9	42.0	
WORKING	46.0	11.0	7.7	5.1	2.6	11.4	8.0	5.2	2.7	11.8	8.3	5.3	2.7	12.2	8.6	5.4	2.8	46.0	
1	50.0	10.8	7.4	5.0	2.6	11.0	7.7	5.1	2.6	11.4	7.9	5.2	2.7	11.0	8.2	5.3	2.7	50.0	1
Ī	54.0	51.0 m/10.8	7.2	4.9	2.5	10.4	7.4	5.0	2.5	9.9	7.6	5.1	2.6	9.5	7.9	5.1	2.6	54.0	1
Ī	58.0		57.1 m/7.1	4.8	2.4	56.3 m/9.7	7.2	4.9	2.5	8.6	7.4	5.0	2.5	8.2	7.6	5.0	2.5	58.0	1
Ī	62.0			4.7	2.4		7.1	4.8	2.4	61.6 m/7.6	7.2	4.9	2.4	7.1	7.4	5.0	2.5	62.0	1
Ī	66.0			63.2 m/4.7	2.4		62.4 m/7.1	4.7	2.4		7.1	4.8	2.4	6.1	6.8	4.9	2.4	66.0	1
ı	70.0				69.3 m/2.4			68.5m/4.6	2.4		67.7 m/6.7	4.7	2.4	66.9 m/5.9	5.9	4.8	2.4	70.0	1
Ī	74.0								2.4			73.8 m/4.6	2.4		73.0 m/5.2	4.8	2.4	74.0	1
Ī	78.0								74.6 m/2.4				2.4			4.7	2.4	78.0	1
İ	82.0												79.9m/2.4			79.1 m/4.6	2.4	82.0	1
ı	86.0																85.1 m/2.4	86.0	1
Re	eves	2	1	1	1	2	1	1	1	2	1	1	1	1	1	1	1	Reev	es

Boo	m length (m)		67	<b>'.1</b>			73	3.2			76	<b>3.</b> 2		Boom leng	th (m)
Jib	length (m)	12.2	18.3	24.4	30.5	12.2	18.3	24.4	30.5	12.2	18.3	24.4	30.5	Jib length	1 (m)
	20.0	20.8 m/13.5				21.9 m/13.5								20.0	
	22.0	13.5				13.5				22.3 m/13.5				22.0	1
	24.0	13.5	24.9 m/12.0			13.5				13.5				24.0	1
	26.0	13.5	11.9			13.5	12.1			13.5	26.5 m/12.0			26.0	1
	28.0	13.5	11.5	28.6 m/6.2		13.5	11.7	29.7 m/6.2		13.5	11.8			28.0	1
	30.0	13.5	11.1	6.1	32.0m/3.3	13.5	11.4	6.2	33.0 m/3.2	13.5	11.5	30.2 m/6.2	33.5 m/3.2	30.0	1
Ē	34.0	13.5	10.4	5.9	3.2	13.5	10.7	6.0	3.2	13.5	10.8	6.0	3.2	34.0	<b>§</b>
radius (m)	38.0	13.5	9.8	5.8	3.0	13.5	10.1	5.8	3.1	13.5	10.2	5.8	3.1	38.0	Working radius (m)
	42.0	13.2	9.3	5.6	2.9	13.5	9.6	5.6	3.0	13.5	9.7	5.7	3.0	42.0	] igra
Working	46.0	12.2	8.9	5.4	2.8	11.7	9.1	5.5	2.9	11.5	9.2	5.5	2.9	46.0	gi gi
Norl	50.0	10.4	8.5	5.3	2.7	10.0	8.7	5.4	2.8	9.7	8.8	5.4	2.8	50.0	] <u>~</u>
ľ	54.0	8.9	8.1	5.2	2.6	8.5	8.4	5.3	2.7	8.2	8.5	5.3	2.7	54.0	]
	58.0	7.6	7.8	5.1	2.6	7.2	8.0	5.2	2.6	6.9	7.7	5.2	2.6	58.0	
	62.0	6.5	7.3	5.0	2.5	6.1	6.9	5.1	2.5	5.8	6.6	5.1	2.5	62.0	]
	66.0	5.6	6.3	5.0	2.4	5.1	5.8	5.0	2.5	4.8	5.6	5.0	2.5	66.0	
	70.0	4.7	5.4	4.9	2.4	4.2	5.0	5.0	2.4	3.9	4.7	5.0	2.4	70.0	]
	74.0	72.2 m/4.3	4.6	4.9	2.4	3.4	4.2	4.7	2.4	3.2	3.9	4.4	2.4	74.0	
	78.0		3.9	4.3	2.4	77.5 m/2.9	3.4	3.9	2.4	2.5	3.2	3.7	2.4	78.0	]
	82.0		78.3 m/3.8	3.7			2.8	3.3			2.5	3.0		82.0	]
	86.0			84.3 m/3.3			83.5 m/2.5	2.7				2.4		86.0	
	90.0							88.0 m/2.4						90.0	
R	eeves	1	1	1	1	1	1	1	1	1	1	1	1	Reev	es

### Note:


Ratings according to Japanese Construction Codes for Mobile Cranes and Japanese Safety Ordinance on Cranes, etc.
Ratings shown in determined by the strength of the boom or other structural compo-Refer to notes P17.



# 13

# **Tower Jib Working Ranges**

Tower Length: 48.8 m




# NOTES:

- Ratings according to Japanese Construction Codes for Mobile Cranes and Japanese Safety Ordinance on Cranes, etc.
- 2. Ratings in metric tons for 360° working area.
- 3. Operating radius is the horizontal distance from center of rotation to a vertical line through the center of gravity of the load.
- Weight of hook block(s), slings and other load handling accessories is included in rated load. Their total weight must be subtracted from rated load to obtain weight that can be lifted.
- 5. Ratings shown are based on freely suspended loads and make no allowance for such factors as wind effect on lifted load, ground conditions out-of-level, operating speeds or any other condition that could be detri-
- mental to the safe operation of this equipment. Operator, therefore, has the responsibility to judge the existing conditions and reduce lifted loads and operating speeds accordingly.
- 6. Ratings are for operation on a firm and level surface.
- At radii and boom lengths where no ratings are shown on chart, operation is not intended nor approved.
- 8. Tower/tower jib inserts and guy lines must be arranged as shown in the "Operator's Manual".
- 9. Tower jib hoist reeving is 8 part line.
- 10. Gantry must be in raised position for all conditions.



# The state of the s

# Tower Length: 64.1 m



- Tower and tower jib backstops are required for all tower and tower jib combinations.
- 12. Ratings shown in \_\_\_\_\_ are determined by the strength of the tower or other structural component.
- 13. When erecting and lowering the tower length of 64.1 m, the pillow plate for erection must be placed at the end of crawlers.
- 14. Instruction in the "Operator's Manual" must be strictly observed when operating the machine.
- 15. Tower jib ratings: Deduct weight of hook block, slings, and all other load handling accessories from tower jib ratings shown.





# **Tower Jib Lifting Capacities**

T	ow	er length (m)				36	5.6				Tower length (	(m)
ľ	Ji	b length (m)		27	.4			30	.5		Jib length (n	n)
Г	T	ower angle	90°	80°	70°	60°	90°	80°	70°	60°	Tower angle	е
ŀ		10.0	10.9m/25.0				11.7 m/25.0				10.0	
		12.0	25.0				25.0				12.0	
ı		14.0	25.0				25.0				14.0	
		16.0	25.0				25.0				16.0	
	_	18.0	25.0				24.2				18.0	<
1	working Hadius (m)	20.0	24.2	21.7 m/23.4			23.5				20.0	Working
1		22.0	23.2	23.2			22.7	23.0 m/21.9			22.0	ing
1	2	24.0	21.0	21.0			21.0	21.0			24.0	Rac
1	<u> </u>	26.0	18.6	18.6			18.6	18.6			26.0	Radius
ı	١	30.0	29.9 m/11.2	15.2	31.9 m/14.1		15.1	15.1	33.7 m/13.0		30.0	(E)
•		34.0		12.8	12.8		32.8 m/10.6	12.7	12.7		34.0	
ı		38.0		36.2 m/11.8	11.1	41.2 m/10.0		11.0	11.0		38.0	
ı		42.0			9.7	9.7		39.2 m/10.6	9.6	43.3 m/9.2	42.0	
		46.0			42.3 m/9.6	8.6			45.2 m/8.7	8.5	46.0	
		50.0				47.9 m/8.2				7.7	50.0	
		54.0								50.8 m/7.6	54.0	
	ĺ	Reeves		2	2			- 2	2		Reeves	

Unit: metric ton

Counterweight: 97.1 t,
Carbody weight: 20.0 t

ω	Tow	er length (m)						39	).7						Tower length (	(m)
39.7	Jil	b length (m)		27	.4			30	).5			33	.5		Jib length (ı	m)
3	T	ower angle	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	Tower angl	le
m Tower		10.0	10.9 m/25.0				11.7 m/25.0								10.0	
er.		12.0	25.0				25.0				12.5 m/25.0				12.0	
뎥		14.0	25.0				25.0				25.0				14.0	
Length		16.0	25.0				25.0				24.2				16.0	
3	ا يا	18.0	25.0				24.2				23.4				18.0	
	Radius (m)	20.0	24.2				23.5				22.6				20.0	Working
	를	22.0	23.2	22.3 m/22.8			22.7	23.6 m/21.4			21.8				22.0	ing
		24.0	20.9	20.9			21.0	20.9			21.0	24.8 m/20.2			24.0	Radius
	<u>₹</u>	26.0	18.5	18.6			18.6	18.6			18.8	18.6			26.0	l iii
	Working	30.0	29.9 m/11.2	15.2	33.0 m/13.4		15.1	15.1			15.3	15.1			30.0	<b>3</b>
		34.0		12.8	12.8		32.8 m/10.6	12.7	34.7 m/12.4		12.0	12.7	36.5 m/11.5		34.0	] [
		38.0		36.7 m/11.5	11.1			11.0	11.0		35.8 m/9.2	11.0	11.0		38.0	
		42.0			9.7	42.7 m/9.5		39.7 m/10.4	9.6	44.9 m/8.7		9.6	9.6		42.0	
		46.0			43.3 m/9.3	8.6			8.5	8.5		42.6 m/9.4	8.4	47.0 m/8.2	46.0	
		50.0				49.4 m/8.0			46.3 m/8.4	7.7			49.2 m/7.7	7.6	50.0	
		54.0								52.4 m/7.2				6.8	54.0	
		56.0												55.3 m/6.6	56.0	
		Reeves		2	2			2	2			2	)		Reeves	

Note:
Ratings according to Japanese
Construction Codes for Mobile
Cranes and Japanese Safety
Ordinance on Cranes, etc.
Ratings shown in \_\_\_\_\_\_
are determined by the strength
of the tower or other structural
components.
Refer to notes P21 and P22.

4:	Tow	er length (m)								42	2.7								Tower length	ı (m)
42.7 m Tower Length	Jil	b length (m)		27	.4			30	).5			33	3.5			36	6.6		Jib length	(m)
3	Te	ower angle	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	Tower and	gle
9		10.0	10.9 m/25.0				11.7 m/25.0												10.0	
er		12.0	25.0				25.0				12.5 m/25.0				13.3 m/23.9				12.0	
Lei		14.0	25.0				25.0				25.0				23.6				14.0	
ngt		16.0	25.0				25.0				24.2				22.9				16.0	
ъ	آ ي	18.0	25.0				24.2				23.4				22.2				18.0	7
	Radius (m)	20.0	24.2				23.5				22.6				21.4				20.0	Working Radius
	ğ	22.0	23.2	22.8 m/22.3			22.7				21.8				20.7				22.0	ging
		24.0	20.9	20.9			21.0	24.1 m/20.9			21.0	25.4 m/19.6			19.9				24.0	Ra
	Working	26.0	18.5	18.6			18.6	18.6			18.8	18.6			18.8	26.7 m/18.2			26.0	∃ius
	Wor	30.0	29.9 m/11.3	15.2			15.1	15.1			15.3	15.1			15.2	15.0			30.0	3
		34.0		12.8	12.8		32.8 m/10.6	12.7	35.8 m/11.8		12.1	12.7			12.8	12.6			34.0	
		38.0		37.3 m/11.4	11.1			11.0	11.0		35.8m/9.2	11.0	11.0		9.3	10.9	39.3 m/10.4		38.0	
		42.0			9.7	44.2 m/9.0		40.2 m/10.2	9.6			9.6	9.6		38.7 m/8.7	9.5	9.5		42.0	
		46.0			44.4 m/8.9	8.6			8.5	46.4 m/8.4		43.2 m/9.3	8.4	48.5 m/7.9		8.4	8.3		46.0	
		50.0				7.8			47.3 m/8.2	7.7			7.5	7.6		46.1 m/8.3	7.4	50.7 m/7.3	50.0	
		54.0				51.0 m/7.6				53.9 m/6.9			50.2 m/7.5	6.8			53.2 m/6.7	6.7	54.0	
		58.0												56.8 m/6.3				6.0	58.0	
		60.0																59.8 m/5.7	60.0	
		Reeves		2	2				2			2	2			2	2		Reeves	3



#### Counterweight: 97.1 t, Carbody weight: 20.0 t Unit: metric ton

4	Tow	er length (m)										45	5.8										Tower length	n (m)
45.8	Jik	length (m)		27	<b>'.4</b>			30	).5			33	3.5			36	6.6			39	).6		Jib length	(m)
3	To	ower angle	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	Tower an	gle
m Tower		10.0	10.9m/25.0				11.7m/25.0																10.0	
		12.0	25.0				25.0				12.5m/25.0				13.3m/23.9								12.0	
Ler		14.0	25.0				25.0				25.0				23.6				14.1m/22.0				14.0	
.ength	L	16.0	25.0				25.0				24.2				22.9				21.4				16.0	
		18.0	25.0				24.2				23.4				22.2				20.8				18.0	
	Ê	20.0	24.2				23.5				22.6				21.4				20.2				20.0	_ ≤
		22.0	23.2	23.3m/21.7			22.7				21.8				20.7				19.6				22.0	Working Radius (m)
	Radius	24.0	20.9	20.9			21.0	24.5m/20.3			21.0	25.9m/18.7			19.9				19.0				24.0	_ ing
		26.0	18.5	18.6			18.6	18.6			18.8	18.6			18.8	27.2m/17.6			18.3	28.5m/16.3			26.0	Rad
	Working	30.0	29.9m/11.3	15.2			15.1	15.1			15.3	15.1			15.2	15.0			15.2	14.9			30.0	lius
	۷	34.0		12.8	35.0m/12.3		32.8m/10.6	12.7	36.8m/11.5		12.1	12.7			12.8	12.6			12.8	12.5			34.0	_ (€
		38.0		37.8m/11.2	11.1			11.0	11.0		35.8m/9.2	11.0	38.5m/10.9		9.3	10.9	40.3m/10.1		10.8	10.8			38.0	
		42.0			9.7	45.8m/8.6		40.7m/10.1	9.6			9.6	9.6		38.7m/8.7	9.5	9.5		41.7m/7.7	9.4	9.4		42.0	
		46.0			45.4m/8.8	8.6			8.5	47.9m/8.1		43.7m/9.1	8.4			8.4	8.3			8.2	8.1		46.0	
	L	50.0				7.8			48.3m/8.1	7.7			7.5	50.1m/7.6		46.6m/8.2	7.4	52.2m/7.0		49.6m/7.2	7.2		50.0	
		54.0				52.5m/7.3				6.9			51.3m/7.3	6.8			6.6	6.7			6.4	54.4m/6.3	54.0	
		58.0								55.4m/6.7				6.1			54.2m/6.6	6.0			57.2m/5.9	5.8	58.0	
		62.0												58.4m/6.0				61.3m/5.5				5.3	62.0	
	ſ	66.0																				64.3m/5.0	66.0	
		Reeves		2	2			2	2				2			2	2			:	2		Reeves	

	_																			
<b>4</b>	Tow	er length (m)								48	3.8								Tower length	(m)
3.8	Jik	length (m)		27	'.4			30	).5			33	3.5			36	.6		Jib length (	(m)
3	To	ower angle	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	Tower ang	le
οŅ		10.0	10.9 m/25.0				11.7 m/25.0												10.0	
er		12.0	25.0				25.0				12.5 m/25.0				13.3 m/23.9				12.0	
Ler		14.0	25.0				25.0				25.0				23.6				14.0	
48.8 m Tower Length		16.0	25.0				25.0				24.2				22.9				16.0	
'n		18.0	25.0				24.2				23.4				22.2				18.0	
	] ۽ ا	20.0	24.2				23.5				22.6				21.4				20.0	
	Working Radius (m)	22.0	23.2	23.9 m/21.2			22.7				21.8				20.7				22.0	Working Radius (m)
	ij	24.0	20.9	20.9			21.0	25.1 m/19.7			21.0				19.9				24.0	ing
	J Pa	26.0	18.5	18.6			18.6	18.6			18.8	26.4 m/18.4			18.8	27.7 m/17.0			26.0	Rac
	ķi	30.0	29.9 m/11.3	15.2			15.1	15.1			15.3	15.1			15.2	15.0			30.0	suik
	Wor	34.0		12.8	36.1 m/11.8		32.8 m/10.6	12.7	37.8 m/11.1		12.1	12.7			12.8	12.6			34.0	<b>3</b>
		38.0		11.1	11.1			11.0	11.0		35.8 m/9.2	11.0	39.6 m/10.3		9.3	10.9	41.3 m/9.6		38.0	
		42.0		38.3 m/11.0	9.7			41.3 m/9.9	9.6			9.6	9.5		38.7 m/8.7	9.5	9.4		42.0	
		46.0			8.6	47.3 m/8.3			8.5	49.4 m/7.8		44.2 m/8.9	8.4			8.4	8.3		46.0	
		50.0			46.4 m/8.5	7.8			49.4 m/7.7	7.7			7.5	51.6 m/7.3		47.2 m/8.1	7.4	53.7 m/6.8	50.0	
		54.0				7.0				6.9			52.3 m/7.1	6.8			6.6	6.7	54.0	
		58.0								56.9 m/6.4				6.1			55.3 m/6.4	6.0	58.0	
		62.0												59.9 m/5.8				5.4	62.0	
		64.0																62.8 m/5.3	64.0	
		Reeves		2	2			2	2			2	2			2	2		Reeves	

Tov	ver length (m)				48	.8				Tower length (	m)
	b length (m)		39	6			42	7		Jib length (n	
_	ower angle	90°	80°	70°	60°	90°	80°	70°	60°	Tower angle	_
i i				70	00			70	00		
	14.0	14.1 m/22.0				14.9 m/20.0				14.0	
	16.0	21.4				19.7				16.0	
	18.0	20.8				19.2				18.0	
	20.0	20.2				18.6				20.0	
	22.0	19.6				18.1				22.0	
_	24.0	19.0				17.5				24.0	_
E	26.0	18.3	29.0 m/15.8			17.0				26.0	Working
ğ	30.0	15.2	14.9			15.2	30.3 m/14.7			30.0	ing
Ba l	34.0	12.8	12.5			12.8	12.4			34.0	Rac
ξij	38.0	10.8	10.8			10.9	10.6			38.0	Radius
Working Radius (m)	42.0	41.7 m/7.7	9.4	43.1 m/9.0		8.9	9.2	44.8 m/8.3		42.0	3
	46.0		8.2	8.1		44.6 m/6.8	8.0	7.9		46.0	Ĭ
	50.0		7.2	7.2			7.0	7.0		50.0	
	54.0		50.1 m/7.1	6.4	55.9 m/6.1		53.0 m/6.4	6.2		54.0	
	58.0			5.8	5.8			5.6	58.1 m/5.6	58.0	
	62.0			58.2 m/5.8	5.3			61.2 m/5.3	5.2	62.0	
	66.0				65.8 m/4.9				4.8	66.0	
	70.0								68.7 m/4.5	70.0	
	Reeves		2	2			2	2		Reeves	

Ratings according to Japanese Construction Codes for Mobile Cranes and Japanese Safety Ordinance on Cranes, etc.

Ratings shown in \_\_\_\_\_\_ are determined by the strength of the tower or other structural components.

Refer to notes P21 and P22.



Unit: metric ton

Counterweight: 97.1	, Carbody	weight: 20.0 t
---------------------	-----------	----------------

رن ت	Tow	er length (m)								51	.9								Tower length	n (m)
51.9	Jil	b length (m)		27	.4			30	.5			33	1.5			36	.6		Jib length	(m)
3	Te	ower angle	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	Tower and	gle
m Tower Length		10.0	10.9 m/25.0				11.7 m/25.0												10.0	
ē		12.0	25.0				25.0				12.5 m/25.0				13.3 m/23.9				12.0	
Fer	[	14.0	25.0				25.0				25.0				23.6				14.0	
1gt		16.0	25.0				25.0				24.2				22.9				16.0	
7		18.0	25.0				24.2				23.4				22.2				18.0	
	_	20.0	24.2				23.5				22.6				21.4				20.0	
	Working Radius (m)	22.0	23.2				22.7				21.8				20.7				22.0	Working Radius
	ij	24.0	20.9	24.4 m/20.6			21.0	25.7 m/19.0			21.0				19.9				24.0	ding
	E.	26.0	18.5	18.6			18.6	18.6			18.8	27.0 m/17.8			18.8	28.2 m/16.6			26.0	Ra
	<u>Ē</u> , [	30.0	29.9 m/11.3	15.2			15.1	15.1			15.3	15.1			15.2	15.0			30.0	] ä
	Š	34.0		12.8	37.1 m/11.4		32.8 m/10.6	12.7			12.1	12.7			12.8	12.6			34.0	3
		38.0		11.1	11.1			11.0	38.9 m/10.7		35.8 m/9.2	11.0	40.6 m/10.0		9.3	10.9			38.0	1
		42.0		38.9 m/10.8	9.7			41.8 m/9.7	9.6			9.6	9.5		38.7 m/8.7	9.5	42.4 m/9.3		42.0	1
		46.0			8.6	48.8 m/8.0			8.5			44.7 m/8.8	8.4			8.4	8.3		46.0	
		50.0			47.5 m/8.2	7.8			7.6	51.0 m/7.5			7.5	53.1 m/7.0		47.7 m/7.9	7.4		50.0	
		54.0				7.0			50.4 m/7.5	6.9			53.4 m/6.9	6.8			6.6	55.3 m/6.4	54.0	
		58.0				55.5 m/6.7				6.2				6.1			56.3 m/6.3	6.0	58.0	
		62.0								58.5 m/6.1				61.4 m/5.6				5.4	62.0	
		66.0																64.4 m/5.1	66.0	
		Reeves		2	2			2	2				2			2	2		Reeves	

To	wer length (m)						51	.9						Tower length	(m)
J	ib length (m)		39	.6			42	2.7			45	.7		Jib length (ı	m)
7	Tower angle	90°	80°	<b>70</b> °	60°	90°	80°	70°	60°	90°	80°	70°	60°	Tower angl	e
Г	14.0	14.1 m/22.0				14.9 m/20.0				15.7 m/17.4				14.0	
	16.0	21.4				19.7				17.4				16.0	
	18.0	20.8				19.2				16.9				18.0	
	20.0	20.2				18.6				16.4				20.0	
	22.0	19.6				18.1				16.0				22.0	
<b>.</b>	24.0	19.0				17.5				15.5				24.0	
Working Radius (m)	26.0	18.3	29.5 m/15.4			17.0				15.0				26.0	Working
를	30.0	15.2	14.9			15.2	30.8 m/14.4			14.1	32.1 m/13.4			30.0	g
Ë	34.0	12.8	12.5			12.8	12.4			12.6	12.3			34.0	Radius
Ě	38.0	10.8	10.8			10.8	10.6			10.6	10.5			38.0	lius
Š	42.0	41.7 m/7.7	9.4	44.1 m/8.7		8.9	9.2	45.9 m/7.9		8.9	9.0			42.0	3
	46.0		8.2	8.1		44.6 m/6.8	8.0	7.9		7.1	7.8	47.6 m/7.4		46.0	
	50.0		7.2	7.2			7.0	7.0		47.5 m/6.1	6.8	6.8		50.0	
	54.0		50.6 m/7.1	6.4	57.4 m/5.9		53.6 m/6.2	6.2			6.0	6.0		54.0	
	58.0			5.8	5.8			5.6	59.6 m/5.3		56.5 m/5.6	5.4	61.7 m/4.8	58.0	
	62.0			59.3 m/5.6	5.2			5.2	5.0			5.0	4.8	62.0	
	66.0				4.8			62.2 m/5.2	4.6			65.2 m/4.6	4.4	66.0	
	70.0				67.3 m/4.6				4.2				4.0	70.0	
	74.0								70.2 m/4.2				73.2 m/3.7	74.0	
	Reeves		2	2			2	2			2	2		Reeves	

Note: Ratings according to Japanese Construction Codes for Mobile Cranes and Japanese Safety Ordinance on Cranes, etc. Ratings shown in \_\_\_\_\_ are determined by the strength of the tower or other structural components. Refer to notes P21 and

P22.

		Heeves							=				-		Heeve		J			
5	Tow	er length (m)								54	.9								Tower length	
1.9	Jib	length (m)		27	.4			30	).5			33	.5			36	6.6		Jib length (	m)
3	To	wer angle	90°	80°	<b>70</b> °	60°	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	Tower ang	le
54.9 m Tower Length		10.0	10.9 m/25.0				11.7 m/25.0												10.0	]
er		12.0	25.0				25.0				12.5 m/25.0				13.3 m/23.9				12.0	
Ler		14.0	25.0				25.0				25.0				23.6				14.0	1 1
gt		16.0	25.0				25.0				24.2				22.9				16.0	4
_		18.0	25.0				24.2				23.4				22.2				18.0	J
	٦	20.0	24.2				23.5				22.6				21.4				20.0	≤
	Working Radius (m)	22.0	23.2				22.7				21.7				20.7				22.0	Working Radius (m)
	ğ	24.0		24.9 m/20.0			21.0				21.0				19.9				24.0	ging
	E E	26.0	18.5	18.6			18.6	26.2 m/18.6			18.8	27.5 m/17.2			18.8	28.8 m/16.2			26.0	⊥ a∂ l
	ă		29.9 m/11.3	15.2			15.1	15.1			15.3	15.1			15.2	15.0			30.0	ü
	Į §	34.0		12.8			32.8 m/10.6	12.7			12.2	12.7			12.8	12.6			34.0	<b> </b> €
		38.0		11.1	38.2 m/11.0			11.0	39.9 m/10.3		35.8 m/9.3	11.0	41.7 m/9.6		9.3	10.9			38.0	4
		42.0		39.4 m/10.6	9.7			9.5	9.6			9.6	9.5		38.7 m/8.7	9.5	43.4 m/9.0		42.0	1
		46.0			8.6			42.3 m/9.5	8.5			45.3 m/8.6	8.4			8.4	8.3		46.0	
		50.0			48.5 m/8.1	50.3 m/7.7			7.6	52.5 m/7.2			7.5			48.2 m/7.8	7.4		50.0	1
		54.0				7.0			51.5 m/7.3	6.9			6.8	54.6 m/6.7			6.6	56.8 m/6.1	54.0	
		58.0				57.0 m/6.4				6.1			54.4 m/6.7	6.0			57.4 m/6.0	5.9	58.0	. I
		62.0								60.0 m/5.8				5.4				5.3	62.0	
		66.0												62.9 m/5.3				65.9 m/4.9	66.0	. I
		Reeves		2	2			2	2			2	2			2	2		Reeves	



# 4 2 5 (C)

Unit: metric ton

Counterweight: 97.1 t, Carbody weight: 20.0 t

Ćι	Tow	er length (m)								54	1.9								Tower length	(m)
54.9 m Tower Length	Jib	length (m)		39	.6			42	2.7			45	5.7			48	3.8		Jib length (	m)
	To	ower angle	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	Tower ang	le
Š.	П	14.0	14.1 m/22.0				14.9 m/20.0				15.7 m/17.4								14.0	
<u>er</u>		16.0	21.4				19.7				17.4				16.5 m/15.4				16.0	1
Le		18.0	20.8				19.2				16.9				15.0				18.0	1
ıgτ		20.0	20.2				18.6				16.4				14.6				20.0	1
_		22.0	19.6				18.1				16.0				14.2				22.0	1
		24.0	19.0				17.5				15.5				13.7				24.0	
	_	26.0	18.3				17.0				15.0				13.3				26.0	1_
	Œ	30.0	15.2	30.1 m/14.9			15.2	31.4 m/14.1			14.1	32.6 m/13.4			12.5	33.9 m/12.1			30.0	Įş
	Radius	34.0	12.8	12.5			12.8	12.4			12.6	12.3			11.6	12.1			34.0	] ĝi
	æ	38.0	10.8	10.8			10.8	10.6			10.6	10.5			10.1	10.2			38.0	湿
	ê,	42.0	41.7 m/7.9	9.4	45.2 m/8.3		8.8	9.2			8.8	9.0			8.6	8.7			42.0	7 ≝
	Working	46.0		8.2	8.1		44.6 m/6.9	8.0	46.9 m/7.7		7.1	7.8	48.7 m/7.1		7.3	7.6			46.0	Working Radius (m)
		50.0		7.2	7.2			7.0	7.0		47.5 m/6.1	6.8	6.8		5.6	6.6	50.4 m/6.5		50.0	1
		54.0		51.2 m/6.9	6.4			6.2	6.2			6.0	6.0		50.5 m/5.3	5.8	5.8		54.0	
		58.0			5.8	58.9 m/5.7		54.1 m/6.2	5.6	61.1 m/5.1		57.0 m/5.5	5.4			5.2	5.2		58.0	1
		62.0			60.3 m/5.6	5.2			5.2	5.0			5.0	63.3 m/4.7		60.0 m/5.0	4.8	65.4 m/4.3	62.0	1
	Ī	66.0				4.8			63.3 m/5.0	4.6			4.6	4.4			4.4	4.2	66.0	1
		70.0				68.8 m/4.5				4.2			66.2 m/4.6	4.0			69.1 m/4.1	3.8	70.0	1
	Ī	74.0								71.8 m/4.0				3.6				3.4	74.0	1
	Ī	78.0												74.7 m/3.5				77.7 m/3.0	78.0	1
	ı	Reeves		2					2			2	2				2		Reeves	1

ي Tov	ver length (m)										58	3.0										Tower length	(m)
58.0 Ji	ib length (m)		27	.4			30	).5			33	3.5			36	6.6			39	9.6		Jib length	(m)
<b>_</b>	ower angle	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	Tower and	jle
m Tower	10.0	10.9m/25.0				11.7m/25.0																10.0	Т
<u>क</u> ्	12.0	25.0				25.0				12.5m/25.0				13.3m/23.9								12.0	
Lenath	14.0	25.0				25.0				25.0				23.6				14.1m/22.0				14.0	
렱	16.0	25.0				25.0				24.2				22.9				21.4				16.0	1
-	18.0	24.9				24.2				23.4				22.2				20.8				18.0	]
	20.0	24.0				23.5				22.6				21.4				20.2				20.0	
	22.0	23.0				22.7				21.7				20.7				19.6				22.0	7 <
Œ)	24.0	20.7	25.4m/19.4			21.0				21.0				19.9				19.0				24.0	Working Radius (m)
Radius	26.0	18.3	18.6			18.6	26.7m/18.1			18.8	28.0m/16.7			18.8	29.3m/15.7			18.3				26.0	ging
	30.0	29.9m/11.3	15.2			15.1	15.1			15.3	15.1			15.2	15.0			15.2	30.6m/14.8			30.0	ੋ ਲੂ
Working	34.0		12.8			32.8m/10.6	12.7			12.2	12.7			12.8	12.6			12.8	12.5			34.0	⊒is
No.	38.0		11.1	39.7m/10.6			11.0	41.0m/10.0		35.8m/9.3	11.0			9.5	10.9			10.7	10.8			38.0	] 3
	42.0		39.9m/10.4	9.7			9.5	9.6			9.6	42.7m/9.2		38.7m/8.9	9.5	44.5m/8.7		41.7m/7.9	9.4			42.0	7
	46.0			8.6			42.9m/9.3	8.5			45.8m/8.5	8.4			8.4	8.3			8.2	46.2m/8.1		46.0	
	50.0			49.6m/7.9	51.8m/7.4			7.6				7.5			48.7m/7.7	7.4			7.2	7.2		50.0	
	54.0				7.0			52.5m/7.2	6.9			6.8	56.2m/6.4			6.6			51.7m/6.8	6.4		54.0	
	58.0				6.2				6.1			55.5m/6.5	6.0			6.0	58.3m/5.8			5.8	60.5m/5.3	58.0	]
	62.0				58.6m/6.1				61.5m/5.6				5.4			58.4m/5.9	5.3			61.3m/5.4	5.1	62.0	
	66.0												64.5m/5.0				4.8				4.6	66.0	
	70.0																67.4m/4.6				4.2	70.0	
	72.0																				70.3m/4.2	72.0	7
	Reeves		2	2				2				2				2				2		Reeves	

_	neeves																	neeve
Tov	ver length (m)								58.0								Tower leng	th (m)
Ji	b length (m)		42	7			45	5.7			48	3.8			51.8		Jib lengt	h (m)
Т	ower angle	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	Tower a	ngle
	14.0	14.9 m/20.0				15.7 m/17.4											14.0	
	16.0	19.7				17.4				16.5 m/15.4				17.2 m/13.9			16.0	
	18.0	19.2				16.9				15.0				13.7			18.0	
	20.0	18.6				16.4				14.6				13.3			20.0	
	22.0	18.1				16.0				14.2				12.8			22.0	
	24.0	17.5				15.5				13.7				12.4			24.0	
-	26.0	17.0				15.0				13.3				12.0			26.0	
Working Radius (m)	30.0	15.2	31.9 m/13.7			14.1	33.2 m/12.7			12.5				11.2			30.0	Working
를	34.0	12.8	12.4			12.6	12.3			11.6	34.5 m/11.8			10.4	35.7 m/10.6		34.0	ing
E E	38.0	10.8	10.6			10.6	10.5			10.1	10.2			9.1	9.7		38.0	Radius
Ě	42.0	8.8	9.2			8.8	9.0			8.6	8.7			7.9	8.4		42.0	iius
Š	46.0	44.6 m/7.0	8.0	48.0 m/7.4		7.1	7.8	49.7 m/6.9		7.3	7.6			6.9	7.3		46.0	<b>E</b>
	50.0		7.0	7.0		47.5 m/6.1	6.8	6.8		5.6	6.6	51.5 m/6.3		5.9	6.4	53.2 m/5.7	50.0	
	54.0		6.2	6.2			6.0	6.0		50.5 m/5.3	5.8	5.8		53.4 m/4.9	5.6	5.6	54.0	
	58.0		54.6 m/6.1	5.6			57.6 m/5.4	5.4			5.2	5.2			5.0	5.0	58.0	
	62.0			5.2	62.6 m/4.8			5.0	64.8 m/4.3		60.5 m/4.9	4.8			4.6	4.6	62.0	
	66.0			64.3 m/4.8	4.4			4.6	4.2			4.4	66.9 m/3.9		63.5 m/4.3	4.2	66.0	
	70.0				4.0			67.2 m/4.4	3.8			4.0	3.6			3.8	70.0	
	74.0				73.3 m/3.6				3.4			70.2 m/4.0	3.2			73.1 m/3.5	74.0	
	78.0								76.2 m/3.2				2.8				78.0	
	80.0												79.2 m/2.7				80.0	
	Reeves		2	2			2	2			2	2			2		Reeves	

Note:

Ratings according to Japanese Construction Codes for Mobile Cranes and Japanese Safety Ordinance on Cranes, etc.

Ratings shown in \_\_\_\_\_ are determined by the strength of the tower or other structural components. Refer to notes P21 and P22.



Unit: metric ton

Counterweight: 97.1 t, Carbody weight: 20.0 t

Tov	ver length (m)										61	1.0										Tower length	(m)
Ji	b length (m)		27	.4			30	.5			33	3.5			36	i.6			39	).6		Jib length	(m)
Т	ower angle	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	Tower ang	jle
	10.0	10.9m/25.0				11.7m/25.0																10.0	
	12.0	25.0				25.0				12.5m/25.0				13.3m/23.9								12.0	
	14.0	25.0				25.0				25.0				23.6				14.1m/22.0				14.0	
	16.0	24.6				24.6				24.0				22.9				21.4				16.0	
	18.0	23.7				23.7				23.0				22.2				20.8				18.0	1
	20.0	22.9				22.7				22.0				21.4				20.2				20.0	1
_	22.0	21.5				21.5				21.0				20.7				19.6				22.0	٦,
E	24.0	20.0				20.0				20.0				19.9				19.0				24.0	Working
Radius	26.0	18.3	18.6			18.6	27.3m/17.4			18.8	28.5m/16.4			18.8	29.8m/15.2			18.3				26.0	ing
Ва	30.0	29.9m/11.3	15.2			15.1	15.1			15.3	15.1			15.2	15.0			15.2	31.1m/14.3			30.0	Radius
Working	34.0		12.8			32.8m/10.6	12.7			12.3	12.7			12.8	12.6			12.8	12.5			34.0	Jius
۷or	38.0		11.1	40.3m/10.3			11.0			35.8m/9.4	11.0			9.5	10.9			10.7	10.8			38.0	3
_	42.0		40.4m/10.2	9.7			9.5	9.6			9.6	43.8m/8.8		38.7m/8.9	9.5	45.5m/8.4		41.7m/7.9	9.4			42.0	<b>7</b>
	46.0			8.6			43.4m/9.2	8.5			8.4	8.4			8.4	8.3			8.2	47.3m/7.8		46.0	
	50.0			7.8	53.4m/6.8			7.6			46.3m/8.4	7.5			49.3m/7.5	7.4			7.2	7.2		50.0	1
	54.0			50.6m/7.7	6.7			53.6m/6.9	55.5m/6.4			6.7	57.7m/5.7			6.6			52.2m/6.8	6.4		54.0	
	58.0				6.1				6.0			56.5m/6.3	5.7			6.0	59.8m/5.3			5.8		58.0	
	62.0				60.1m/5.8				5.4				5.2			59.4m/5.8	5.1			5.4	4.9	62.0	
	66.0								63.0m/5.2				4.8				4.7			62.4m/5.3	4.5	66.0	1
	70.0																68.9m/4.3				3.9	70.0	
	74.0																				71.9m/3.6	74.0	1
i	Reeves		- 2					2				2			2					2		Reeves	

Tov	ver length (m)								61.0								Tower length	(m)
_	b length (m)		42	.7			45	.7	0110		48	3.8			51.8		Jib length (	• •
_	ower angle	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	Tower ang	
	14.0	14.9 m/20.0				15.7 m/17.4											14.0	
	16.0	19.7				17.4				16.5 m/15.4				17.2 m/13.9			16.0	
	18.0	19.2				16.9				15.0				13.7			18.0	
	20.0	18.6				16.4				14.6				13.3			20.0	
	22.0	18.1				16.0				14.2				12.8			22.0	
	24.0	17.5				15.5				13.7				12.4			24.0	
<u>-</u>	26.0	17.0				15.0				13.3				12.0			26.0	_ <
s (m)	30.0	15.2	32.4 m/13.5			14.1	33.7 m/12.6			12.5				11.2			30.0	Working
Working Radius	34.0	12.8	12.4			12.6	12.3			11.6	35.0 m/11.4			10.4	36.3 m/9.7		34.0	gil
J Re	38.0	10.8	10.6			10.4	10.5			9.9	10.1			9.1	9.3		38.0	Radius
ķi	42.0	8.9	9.2			8.7	9.0			8.5	8.6			7.9	8.2		42.0	
Wor	46.0	44.6 m/6.9	8.0	49.0 m/7.2		7.2	7.8			7.3	7.5			6.9	7.1		46.0	3
	50.0		7.0	7.0		47.5 m/6.2	6.8	50.8 m/6.7		5.6	6.5	52.5 m/6.0		5.8	6.2		50.0	] [
	54.0		6.2	6.2			6.0	6.0		50.5 m/5.3	5.7	5.7		53.4 m/4.9	5.4	54.2 m/5.3	54.0	
	58.0		55.2 m/5.9	5.6			5.4	5.4			5.1	5.1			4.8	4.8	58.0	
	62.0			5.2	64.1 m/4.0		58.1 m/5.4	5.0			61.0 m/4.7	4.7			4.4	4.4	62.0	
	66.0			65.3 m/4.9	4.0			4.6	66.3 m/3.7			4.3			64.0 m/4.1	4.0	66.0	
	70.0				3.6			68.3 m/4.3	3.3			3.9	3.1			3.6	70.0	
	74.0				3.2				2.9			71.2 m/3.8	2.7			3.2	74.0	]
	78.0				74.8 m/3.1				77.8 m/2.5				2.3			74.2 m/3.2	78.0	
	Reeves		2	2			2	2			- 2	2			2		Reeves	

Ratings according to Japanese Construction Codes for Mobile Cranes and Japanese Safety Ordinance on Cranes, etc.

Ratings shown in \_\_\_\_\_\_are determined by the strength of the tower or other structural components.

Refer to notes P21 and P22.



Unit: metric ton

Counterweight: 97.1 t, Carbody weight: 20.0 t

ο T	ower le	ength (m)										64	l.1										Tower length (	m)
64.1	Jib le	ngth (m)		27	.4			30.	5 m			33	3.5			36	6.6			39	9.6		Jib length (ı	m)
3	Towe	er angle	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	90°	80°	70°	60°	Tower angl	е
Tower Length		10.0	10.9m/25.0				11.7m/25.0																10.0	
/er		12.0	25.0				25.0				12.5m/24.8				13.3m/23.9								12.0	
Ē		14.0	24.3				24.3				24.3				23.6				14.1m/22.0				14.0	
ngt		16.0	23.6				23.6				23.6				22.9				21.4				16.0	
5		18.0	22.9				22.9				22.9				22.2				20.8				18.0	
		20.0	22.2				22.2				22.0				21.4				20.2				20.0	
	_	22.0	21.5				21.5				21.0				20.7				19.6				22.0	<
	E –	24.0	20.0				20.0				20.0				19.9				19.0				24.0	Working
į.	Hadins	26.0	18.3	26.5m/18.3			18.6	27.8m/15.9			18.8	29.1m/15.9			18.8				18.3				26.0	gii
Ġ	2	30.0	29.9m/11.3	15.2			15.1	15.1			15.3	15.1			15.2	30.4m/14.9			15.2	31.7m/13.9			30.0	Radius (m)
	Working	34.0		12.8			32.8m/10.6	12.7			12.3	12.7			12.8	12.6			12.8	12.5			34.0	l iii
	No.	38.0		11.1	41.3m/9.9			11.0			35.8m/9.4	11.0			9.5	10.9			10.7	10.8			38.0	3
		42.0		41.0m/10.0	9.7			9.5	43.1m/9.3			9.6	44.8m/8.7		38.7m/8.9	9.5			41.7m/7.9	9.4			42.0	
		46.0			8.6			43.9m/9.0	8.5			8.4	8.4			8.4	46.5m/8.1			8.2	48.3m/7.6		46.0	
		50.0			7.8				7.6			46.9m/8.2	7.5			49.8m/7.4	7.4			7.2	7.2		50.0	
		54.0			51.7m/7.4	54.9m/6.0			6.9	57.1m/5.4			6.7				6.6			52.7m/6.6	6.4		54.0	
		58.0				5.7			54.6m/6.7	5.3			57.5m/6.2	59.2m/4.9			6.0	61.4m/4.5			5.8		58.0	
		62.0				61.6m/5.3				4.9				4.6			60.5m/5.6	4.4			5.4	63.5m/4.0	62.0	
		66.0								64.6m/4.6				4.2				4.0			63.4m/5.3	3.8	66.0	
		70.0												67.5m/4.0				3.6				3.4	70.0	
		74.0																70.5m/3.5				73.4m/3.0	74.0	
	F	Reeves		2	2			- 2	2				2			2	2				2		Reeves	

Tower length (m)		64.1										Tower length	(m)			
Jib length (m)		42.7			45.7		48.8			51.8		Jib length (m)				
Tower angle		90°	80°	70°	60°	90°	80°	70°	90°	80°	70°	90°	80°	70°	Tower ang	le
	14.0	14.9 m/20.0				15.7 m/17.4									14.0	
	16.0	19.7				17.4			16.5 m/15.4			17.2 m/13.9			16.0	
	18.0	19.2				16.9			15.0			13.7			18.0	
	20.0	18.6				16.4			14.6			13.3			20.0	
	22.0	18.1				16.0			14.2			12.8			22.0	
	24.0	17.5				15.5			13.7			12.4			24.0	
<u> </u>	26.0	17.0				15.0			13.3			11.9			26.0	_ <
Working Radius (m)	30.0	15.2	32.9 m/13.3			14.1			12.5			11.1			30.0	Working
	34.0	12.8	12.4			12.6	34.2 m/12.3		11.6	35.5 m/11.4		10.4	36.8 m/9.2		34.0	
	38.0	10.8	10.6			10.4	10.5		9.9	10.1		9.1	9.0		38.0	Ba
	42.0	8.8	9.2			8.7	9.0		8.5	8.6		7.9	7.9		42.0	Radius
	46.0	44.6 m/6.9	8.0			7.1	7.8		7.1	7.5		6.8	6.8		46.0	3
	50.0		7.0	7.0		47.5 m/6.2	6.8	51.8 m/6.4	5.6	6.5	53.5 m/5.8	5.6	5.9		50.0	
	54.0		6.1	6.2			6.0	6.0	50.5 m/5.3	5.7	5.7	53.4 m/4.5	5.1	55.3 m/4.9	54.0	
	58.0		55.7 m/5.8	5.6			5.4	5.4		5.1	5.1		4.5	4.5	58.0	1
	62.0			5.2			58.6 m/5.3	5.0		61.6 m/4.7	4.7		4.1	4.1	62.0	
	66.0			4.8	3.4			4.6			4.3		64.5 m/3.7	3.7	66.0	
	70.0			66.4 m/4.7	3.2			69.3 m/4.3			3.9			3.3	70.0	
	74.0				2.8						72.3 m/3.7			3.0	74.0	
	78.0													75.2 m/2.9	78.0	
	Reeves		2	)			2			2			2		Reeves	

Ν	ote


Ratings according to Japanese Construction Codes for Mobile Cranes and Japanese Safety Ordinance on Cranes, etc.
Ratings shown in \_\_\_\_\_\_are determined by the strength of the tower or other structural components.
Refer to notes P21 and P22.



# **PARTS AND ATTACHMENTS**


#### **Base Machine**


With boom base, carbody, gantry, trans-lifter, lower spreader, and upper spreader, main and aux. winches (non free-fall) including wire rope and boom hoist winch including wire rope
Weight: 44,500 kg Width: 3,400 mm




#### **Base Machine**

With carbody, gantry, trans-lifter, main and aux. winches (non free-fall) and boom hoist winch Without lower spreader, wire rope for boom hoist, and wire rope for main and aux. hoist Weight: 37,300 kg Width: 3,200 mm





Dimensions: mm Weight: kg




	L (mm)	Weight (kg)*		
3.0m	3,175	890		
6.1m	6,220	1,440		
12.2m	12,320	2,540		

<sup>\*</sup>with boom guy cables

# Boom Base (with backstop)


Weight: 4,180 kg






# **Boom Top**

Weight: 3,860 kg




## Insert Tapered Boom

Weight: 1,160 kg




# Gantry Weight: 2,830 kg




# Counterweight A Weight: 13,500 kg 5,000








# Counterweight B, C, D Weight: 13,200 kg





# Counterweight F, F' Weight: 11,000 kg




#### Carbodyweight Weight: 10,000 kg x 2






Dimensions: mm Weight: kg

# **Jib Base with Strut (For Crane)** Weight: 510 kg Width: 1,040 mm




# Jib Top (For Crane) Weight: 315 kg



# 9.1 m Special Insert Boom for Tower

Weight: 2,200 kg






# **Tower Cap**








Insert Tower Jib



	L (mm)	Weight (kg)		
3.0 m	3,160	320		
6.1 m	6,210	530		
9.1 m	9,260	740		

### Tower Jib Base

Weight: 1,710 kg



# **Tower Jib Top**

Weight: 1,120 kg




# **Other Attachments**

Attachments	Weight	Dimensions (L x W x H)		
3.0 m insert jib (for crane)	110 kg	3,130 mm x 1,020 mm x 840 mm		
6.1 m insert jib (for crane)	190 kg	6,175 mm x 1,020 mm x 840 mm		
Relay jib	400 kg (with guy cables)	3,170 mm x 1,670 mm x 1,690 mm		
Trans-lifter	395 kg	1,145 mm x 400 mm x 1,390 mm		
Upper spreader	670 kg	2,410 mm x 250 mm x 890 mm		
Lower spreader	400 kg	1,500 mm x 290 mm x 760 mm		
Tower strut	2,190 kg	7,165 mm x 1,150 mm x 2,430 mm		
Upper spreader for tower jib	260 kg	1,020 mm x 335 mm x 765 mm		
Lower spreader for tower jib	490 kg	2,330 mm x 705 mm x 1,090 mm		
250-ton hook	4,200 kg	2,310 mm x 1,620 mm x 720 mm		
150-ton hook	2,300 kg	715 mm x 700 mm x 2,250 mm		
70-ton hook	1,200 kg	380 mm x 700 mm x 1,825 mm		
35-ton hook	900 kg	365 mm x 700 mm x 1,575 mm		
Ball hook	450 kg	1,200 mm x 380 mm dia.		

Note: Estimated weights may vary ± 2%.

# **Transportation of Base Machine**



- 1. Rest the lower boom on the wooden block.
- 2. This transportation plan depends on specifications of your trailer and the areas or countries where you tansport.





**Safety Device** 

LCD multi display

Function lock lever

Swing parking brake

Swing flashers/warning buzzer

Propel lever lock

Signal horn

Load Moment Indicator (with boom lowering slow stop function)

LMI release key (for hook over-hoist prevention device and

Mechanical drum lock pawl (main, aux. and boom hoist)

boom over-hoist prevention device)

Ultimate stop function for boom over-hoist

Mechanical swing lock pin (four positions)

# **Standard Equipment**

# Upper structure/Lower structure

Counterweight: 97.1 ton (total weight) Carbody weight: 20.0 ton (total weight)

1,070 mm shoe crawlers Batteries (136Ah/5HR) Trans-lifter (jack system)

Gantry raising/lowering cylinder (with storage chain)

Electric hand throttle grip

Variable boom hoist speed controller Variable main/aux. hoist speed controller Swing neutral-free/brake select switch

Swing neutral-free/brake select switch Side deck for cab

Steps (crawlers)
Two front working lights
Two rear view mirrors

Tools (for routine maintenance)

Boom connect pin holder

Cable roller (for boom)

Upper spreader storage guide

Level gauge (carbody)

### **Cab Control**

Air conditioner

Luggage box

Cup holder

Ashtray

Cigar lighter

Intermittent wiper & window washer (skylight and front window)

Sun visor Roof blind

Floor mat (cloth)

Foot rest

Shoe tray

# Bigge Crane and Rigging Co.

10700 Bigge Avenue San Leandro, CA 94577

Phone: (888) 337-BIGGE or (510) 638-8100

Fax: (510) 639-4053 Email: info@bigge.com Web site: www.bigge.com

Note: Standard equipment may vary depending on your areas or countries.

Due to our policy of continual product improvements all designs and specifications are subject to change without advance notice.

Copyright by KOBELCO CRANES CO., LTD. No part of this catalog may be reproduced in any manner without notice.

# **KOBELCO CRANES CO., LTD.**

17-1, Higashigotanda 2-chome, Shinagawa-ku, Tokyo 141-8626 JAPAN Tel: +81-3-5789-2130 Fax: +81-3-5789-3372

KOBELCO is the corporate mark used by Kobe Steel on a variety of product
and in the names of a number of Kobe Steel Group companies.

Inquiries To:			

Bulletin No. 7250-2FSPEC-AO3 080201IF Printed in Japan

(909) 222-0202